

PATENT COOPERATION TREATY

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

From the INTERNATIONAL BUREAU

To:

Assistant Commissioner for Patents
United States Patent and Trademark
Office
Box PCT
Washington, D.C.20231
ETATS-UNIS D'AMERIQUE

in its capacity as elected Office

Date of mailing (day/month/year) 12 April 2000 (12.04.00)	
International application No. PCT/IT99/00262	Applicant's or agent's file reference RM/X89340/PC
International filing date (day/month/year) 11 August 1999 (11.08.99)	Priority date (day/month/year) 12 August 1998 (12.08.98)
Applicant ARCIERI, Franco et al	

1. The designated Office is hereby notified of its election made:

☒ in the demand filed with the International Preliminary Examining Authority on:
09 March 2000 (09.03.00)

☐ in a notice effecting later election filed with the International Bureau on:

2. The election ☒ was

☐ was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

<p>The International Bureau of WIPO 34, chemin des Colombettes 1211 Geneva 20, Switzerland</p> <p>Facsimile No.: (41-22) 740.14.35</p>	<p>Authorized officer</p> <p>Olivia RANAIVOJAONA</p> <p>Telephone No.: (41-22) 338.83.38</p>
--	--

09/762540

The demand must be filed directly with the competent International Preliminary Examining Authority or, if two or more Authorities are competent, with the one chosen by the applicant. The full name or two-letter code of that Authority may be indicated by the applicant on the line below:

IPEA/ EP

PCT

CHAPTER II

DEMAND

under Article 31 of the Patent Cooperation Treaty:
The undersigned requests that the international application specified below be the subject of international preliminary examination according to the Patent Cooperation Treaty and hereby elects all eligible States (except where otherwise indicated).

For International Preliminary Examining Authority use only

Identification of IPEA		Date of receipt of DEMAND	
Box No. I IDENTIFICATION OF THE INTERNATIONAL APPLICATION		Applicant's or agent's file reference RM/X89340/PC	
International application No. PCT/IT99/00262	International filing date (day/month/year) 11 August 1999	(Earliest) Priority date (day/month/year) 11 August 1998	
Title of invention Network access control device through fast recognition of application frames			
Box No. II APPLICANT(S)			
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.) ALASI DI ARCIERI FRANCO & C. s.a.s. Via Mario Chiri 25 00171 Roma ITALY		Telephone No.: Facsimile No.: Teleprinter No.:	
State (that is, country) of nationality: ITALY		State (that is, country) of residence: ITALY	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.) ARCIERI Franco Via Mario Chiri 25 00171 Roma ITALY			
State (that is, country) of nationality: ITALY		State (that is, country) of residence: ITALY	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.) MARINELLI Guido Maria Via Squillace 108 00178 Roma ITALY			
State (that is, country) of nationality: ITALY		State (that is, country) of residence: ITALY	
<input checked="" type="checkbox"/> Further applicants are indicated on a continuation sheet.			

Continuation of Box No. II APPLICANT(S)

If none of the following sub-boxes is used, this sheet should not be included in the demand

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

TALAMO Maurizio
Via Emanuele Filiberto 233
00185 Roma
ITALY

State *(that is, country)* of nationality:

ITALY

State *(that is, country)* of residence:

ITALY

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

State *(that is, country)* of nationality:

State *(that is, country)* of residence:

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

State *(that is, country)* of nationality:

State *(that is, country)* of residence:

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

State *(that is, country)* of nationality:

State *(that is, country)* of residence:



Further applicants are indicated on another continuation sheet.

Box No. III AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCEThe following person is ☒ agent ☐ common representativeand ☒ has been appointed earlier and represents the applicant(s) also for international preliminary examination.☐ is hereby appointed and any earlier appointment of (an) agent(s)/common representative is hereby revoked.☐ is hereby appointed, specifically for the procedure before the International Preliminary Examining Authority, in addition to the agent(s)/common representative appointed earlier.Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*LEONE Mario
Società Italiana Brevetti S.p.A.
Piazza di Pietra 39
00186 Roma
ITALY

Telephone No.:

+39-06-695441

Facsimile No.:

+39-06-6955830

Teleprinter No.:

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.**Box No. IV BASIS FOR INTERNATIONAL PRELIMINARY EXAMINATION****Statement concerning amendments:***

1. The applicant wishes the international preliminary examination to start on the basis of:

☒ the international application as originally filedthe description ☐ as originally filed☐ as amended under Article 34the claims ☐ as originally filed☐ as amended under Article 19 (together with any accompanying statement)☐ as amended under Article 34the drawings ☐ as originally filed☐ as amended under Article 342. ☐ The applicant wishes any amendment to the claims under Article 19 to be considered as reversed.3. ☐ The applicant wishes the start of the international preliminary examination to be postponed until the expiration of 20 months from the priority date unless the International Preliminary Examining Authority receives a copy of any amendments made under Article 19 or a notice from the applicant that he does not wish to make such amendments (Rule 69.1(d)). *(This check-box may be marked only where the time limit under Article 19 has not yet expired.)*

* Where no check-box is marked, international preliminary examination will start on the basis of the international application as originally filed or, where a copy of amendments to the claims under Article 19 and/or amendments of the international application under Article 34 are received by the International Preliminary Examining Authority before it has begun to draw up a written opinion or the international preliminary examination report, as so amended.

Language for the purposes of international preliminary examination: ENGLISH☒ which is the language in which the international application was filed.☐ which is the language of a translation furnished for the purposes of international search.☐ which is the language of publication of the international application.☐ which is the language of the translation (to be) furnished for the purposes of international preliminary examination.**Box No. V ELECTION OF STATES**The applicant hereby elects all eligible States *(that is, all States which have been designated and which are bound by Chapter II of the PCT)*

excluding the following States which the applicant wishes not to elect:

Box No. VI CHECK LIST

The demand is accompanied by the following elements, in the language referred to in Box No. IV, for the purposes of international preliminary examination:

- | | | |
|--|---|--------|
| 1. translation of international application | : | sheets |
| 2. amendments under Article 34 | : | sheets |
| 3. copy (or, where required, translation) of amendments under Article 19 | : | sheets |
| 4. copy (or, where required, translation) of statement under Article 19 | : | sheets |
| 5. letter | : | sheets |
| 6. other (<i>specify</i>) | : | sheets |

For International Preliminary
Examining Authority use only

received not received

<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>


The demand is also accompanied by the item(s) marked below:

- | | |
|--|---|
| 1. <input checked="" type="checkbox"/> fee calculation sheet | 4. <input type="checkbox"/> statement explaining lack of signature |
| 2. <input type="checkbox"/> separate signed power of attorney | 5. <input type="checkbox"/> nucleotide and or amino acid sequence listing in computer readable form |
| 3. <input type="checkbox"/> copy of general power of attorney; reference number, if any: | 6. <input type="checkbox"/> other (<i>specify</i>): |

Box No. VII SIGNATURE OF APPLICANT, AGENT OR COMMON REPRESENTATIVE

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the demand).

LEONE Mario



For International Preliminary Examining Authority use only

1. Date of actual receipt of DEMAND:

2. Adjusted date of receipt of demand due to CORRECTIONS under Rule 60.1(b):

3. ☐ The date of receipt of the demand is AFTER the expiration of 19 months from the priority date and item 4 or 5, below, does not apply.

☐ The applicant has been informed accordingly.

4. ☐ The date of receipt of the demand is WITHIN the period of 19 months from the priority date as extended by virtue of Rule 80.5.

5. ☐ Although the date of receipt of the demand is after the expiration of 19 months from the priority date, the delay in arrival is EXCUSED pursuant to Rule 82.

For International Bureau use only

Demand received from IPEA on:

00/1700510

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No.

International Filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum) RM/X89340/PC

Box No. I TITLE OF INVENTION
Network access control device through fast recognition of application frames satisfying a set of predetermined rules

Box No. II APPLICANT

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

ALASI DI ARCIERI FRANCO & C. s.a.s.
Via Mario Chiri 25
00171 Roma
ITALY

☐ This person is also inventor.

Telephone No.

Facsimile No.

Teleprinter No.

State (that is, country) of nationality:
ITALYState (that is, country) of residence:
ITALY

This person is applicant for the purposes of: ☐ all designated States ☒ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

ARCIERI Franco
Via Mario Chiri 25
00171 Roma
ITALY

This person is:

☐ applicant only☒ applicant and inventor☐ inventor only (If this check-box is marked, do not fill in below.)State (that is, country) of nationality:
ITALYState (that is, country) of residence:
ITALY

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on a continuation sheet.**Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE**

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: ☒ agent ☐ common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

STEINFL Alessandro
Società Italiana Brevetti S.p.A.
Piazza di Pietra 39
00186 Roma
ITALY

Telephone No.

+39-06-695441

Facsimile No.

+39-06-69544830

Teleprinter No.

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Continuation of Box No. III FURTHER APPLICANTS AND/OR (FURTHER) INVENTORS

If none of the following sub-boxes is used, this sheet should not be included in the request.

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

MARINELLI Guido Maria
Via Squillace 108
00178 Roma
ITALY

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:
ITALY

State (that is, country) of residence:
ITALY

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

TALAMO Maurizio
Via Emanuele Filiberto 233
00185 Roma
ITALY

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:
ITALY

State (that is, country) of residence:
ITALY

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on another continuation sheet.

Box No.V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent

- ☒ **AP ARIPO Patent:** GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SL Sierra Leone, SZ Swaziland, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☒ **EA Eurasian Patent:** AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ **EP European Patent:** AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☒ **OA OAPI Patent:** BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line)

- | | |
|---|--|
| <input checked="" type="checkbox"/> AE United Arab Emirates | <input checked="" type="checkbox"/> LR Liberia |
| <input checked="" type="checkbox"/> AL Albania | <input checked="" type="checkbox"/> LS Lesotho |
| <input checked="" type="checkbox"/> AM Armenia | <input checked="" type="checkbox"/> LT Lithuania |
| <input checked="" type="checkbox"/> AT Austria | <input checked="" type="checkbox"/> LU Luxembourg |
| <input checked="" type="checkbox"/> AU Australia | <input checked="" type="checkbox"/> LV Latvia |
| <input checked="" type="checkbox"/> AZ Azerbaijan | <input checked="" type="checkbox"/> MD Republic of Moldova |
| <input checked="" type="checkbox"/> BA Bosnia and Herzegovina | <input checked="" type="checkbox"/> MG Madagascar |
| <input checked="" type="checkbox"/> BB Barbados | <input checked="" type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input checked="" type="checkbox"/> BG Bulgaria | <input checked="" type="checkbox"/> MN Mongolia |
| <input checked="" type="checkbox"/> BR Brazil | <input checked="" type="checkbox"/> MW Malawi |
| <input checked="" type="checkbox"/> BY Belarus | <input checked="" type="checkbox"/> MX Mexico |
| <input checked="" type="checkbox"/> CA Canada | <input checked="" type="checkbox"/> NO Norway |
| <input checked="" type="checkbox"/> CH and LI Switzerland and Liechtenstein | <input checked="" type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> CN China | <input checked="" type="checkbox"/> PL Poland |
| <input checked="" type="checkbox"/> CU Cuba | <input checked="" type="checkbox"/> PT Portugal |
| <input checked="" type="checkbox"/> CZ Czech Republic | <input checked="" type="checkbox"/> RO Romania |
| <input checked="" type="checkbox"/> DE Germany | <input checked="" type="checkbox"/> RU Russian Federation |
| <input checked="" type="checkbox"/> DK Denmark | <input checked="" type="checkbox"/> SD Sudan |
| <input checked="" type="checkbox"/> EE Estonia | <input checked="" type="checkbox"/> SE Sweden |
| <input checked="" type="checkbox"/> ES Spain | <input checked="" type="checkbox"/> SG Singapore |
| <input checked="" type="checkbox"/> FI Finland | <input checked="" type="checkbox"/> SI Slovenia |
| <input checked="" type="checkbox"/> GB United Kingdom | <input checked="" type="checkbox"/> SK Slovakia |
| <input checked="" type="checkbox"/> GD Grenada | <input checked="" type="checkbox"/> SL Sierra Leone |
| <input checked="" type="checkbox"/> GE Georgia | <input checked="" type="checkbox"/> TJ Tajikistan |
| <input checked="" type="checkbox"/> GH Ghana | <input checked="" type="checkbox"/> TM Turkmenistan |
| <input checked="" type="checkbox"/> GM Gambia | <input checked="" type="checkbox"/> TR Turkey |
| <input checked="" type="checkbox"/> HR Croatia | <input checked="" type="checkbox"/> TT Trinidad and Tobago |
| <input checked="" type="checkbox"/> HU Hungary | <input checked="" type="checkbox"/> UA Ukraine |
| <input checked="" type="checkbox"/> ID Indonesia | <input checked="" type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> IL Israel | <input checked="" type="checkbox"/> US United States of America |
| <input checked="" type="checkbox"/> IN India | <input checked="" type="checkbox"/> UZ Uzbekistan |
| <input checked="" type="checkbox"/> IS Iceland | <input checked="" type="checkbox"/> VN Viet Nam |
| <input checked="" type="checkbox"/> JP Japan | <input checked="" type="checkbox"/> YU Yugoslavia |
| <input checked="" type="checkbox"/> KE Kenya | <input checked="" type="checkbox"/> ZA South Africa |
| <input checked="" type="checkbox"/> KG Kyrgyzstan | <input checked="" type="checkbox"/> ZW Zimbabwe |
| <input checked="" type="checkbox"/> KP Democratic People's Republic of Korea | |
| <input checked="" type="checkbox"/> KR Republic of Korea | Check-boxes reserved for designating States which have become party to the PCT after issuance of this sheet: |
| <input checked="" type="checkbox"/> KZ Kazakhstan | <input checked="" type="checkbox"/> CR Costa Rica |
| <input checked="" type="checkbox"/> LC Saint Lucia | <input checked="" type="checkbox"/> DM Dominica |
| <input checked="" type="checkbox"/> LK Sri Lanka | |

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)

Supplemental Box *If the Supplemental Box is not used, this sheet should not be included in the request.*

1. If, in any of the Boxes, the space is insufficient to furnish all the information: in such case, write "Continuation of Box No. ..." [indicate the number of the Box] and furnish the information in the same manner as required according to the captions of the Box in which the space was insufficient, in particular:

- (i) if more than two persons are involved as applicants and/or inventors and no "continuation sheet" is available: in such case, write "Continuation of Box No. III" and indicate for each additional person the same type of information as required in Box No. III. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below;
- (ii) if, in Box No. II or in any of the sub-boxes of Box No. III, the indication "the States indicated in the Supplemental Box" is checked: in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the applicant(s) involved and, next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is applicant;
- (iii) if, in Box No. II or in any of the sub-boxes of Box No. III, the inventor or the inventor/applicant is not inventor for the purposes of all designated States or for the purposes of the United States of America: in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the inventor(s) and, next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is inventor;
- (iv) if, in addition to the agent(s) indicated in Box No. IV, there are further agents: in such case, write "Continuation of Box No. IV" and indicate for each further agent the same type of information as required in Box No. IV;
- (v) if, in Box No. V, the name of any State (or OAPI) is accompanied by the indication "patent of addition," or "certificate of addition," or if, in Box No. V, the name of the United States of America is accompanied by an indication "continuation" or "continuation-in-part": in such case, write "Continuation of Box No. V" and the name of each State involved (or OAPI), and after the name of each such State (or OAPI), the number of the parent title or parent application and the date of grant of the parent title or filing of the parent application;
- (vi) if, in Box No. VI, there are more than three earlier applications whose priority is claimed: in such case, write "Continuation of Box No. VI" and indicate for each additional earlier application the same type of information as required in Box No. VI;
- (vii) if, in Box No. VI, the earlier application is an ARIPO application: in such case, write "Continuation of Box No. VI", specify the number of the item corresponding to that earlier application and indicate at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed.


2. If, with regard to the precautionary designation statement contained in Box No. V, the applicant wishes to exclude any State(s) from the scope of that statement: in such case, write "Designation(s) excluded from precautionary designation statement" and indicate the name or two-letter code of each State so excluded.

3. If the applicant claims, in respect of any designated Office, the benefits of provisions of the national law concerning non-prejudicial disclosures or exceptions to lack of novelty: in such case, write "Statement concerning non-prejudicial disclosures or exceptions to lack of novelty" and furnish that statement below.

CONTINUATION OF BOX NO. 4

ADORNO Silvano, AIMI Luciano, BARDINI Marco Luigi, BAZZICHELLI Alfredo, BORRINI Stefano,
CONCONE Emanuele, DE BENEDETTI Fabrizio, DI CERBO Mario, IACOBELLI Daniele, LEONE Mario,
MOSCONE BENVENUTI Francesca, PELLEGRINI Alberto, PIZZOLI Antonio Maria, PIZZOLI Pasquale,
STRINI Giorgio, TONON Gilberto

Società Italiana Brevetti S.p.A.
Piazza di Pietra 39
00186 Roma
Italy

Box No. VI PRIORITY CLAIM		<input type="checkbox"/> Further priority claims are indicated in the Supplemental Box.		
Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	regional application: regional Office	international application: receiving Office
item (1) 12 August 1998	RM98A000542	ITALY		
item (2)				
item (3)				
<input type="checkbox"/> The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s): _____				
<small>* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.</small>				
Box No. VII INTERNATIONAL SEARCHING AUTHORITY				
Choice of International Searching Authority (ISA) <small>(if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):</small>		Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):		
ISA /		Date (day/month/year)	Number	Country (or regional Office)
Box No. VIII CHECK LIST; LANGUAGE OF FILING				
This international application contains the following number of sheets: request : 5 description (excluding sequence listing part) : 46 claims : 4 abstract : 1 drawings : 12 sequence listing part of description : _____ Total number of sheets : 68		This international application is accompanied by the item(s) marked below: 1. <input type="checkbox"/> fee calculation sheet 2. <input checked="" type="checkbox"/> separate signed power of attorney 3. <input type="checkbox"/> copy of general power of attorney; reference number, if any: 4. <input type="checkbox"/> statement explaining lack of signature 5. <input checked="" type="checkbox"/> priority document(s) identified in Box No. VI as item(s): 6. <input type="checkbox"/> translation of international application into (language): 7. <input type="checkbox"/> separate indications concerning deposited microorganism or other biological material 8. <input type="checkbox"/> nucleotide and/or amino acid sequence listing in computer readable form 9. <input type="checkbox"/> other (specify):		
Figure of the drawings which should accompany the abstract: 9		Language of filing of the international application: ENGLISH		
Box No. IX SIGNATURE OF APPLICANT OR AGENT				
Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).				
Alessandro STEINFL 				

For receiving Office use only	
1. Date of actual receipt of the purported international application: 3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application: 4. Date of timely receipt of the required corrections under PCT Article 11(2): 5. International Searching Authority (if two or more are competent): ISA /	2. Drawings: <input type="checkbox"/> received: <input type="checkbox"/> not received: 6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid.

For International Bureau use only
Date of receipt of the record copy by the International Bureau:

PATENT COOPERATION TREATY 09 / 7 6 2 5 4 0

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)



Applicant's or agent's file reference RM/X89340/PC	FOR FURTHER ACTION		See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)
International application No. PCT/IT99/00262	International filing date (<i>day/month/year</i>) 11/08/1999	Priority date (<i>day/month/year</i>) 12/08/1998	
International Patent Classification (IPC) or national classification and IPC H04L29/06			
Applicant ALASI DI ARCIERI FRANCO & C. S.A.S. et al.			

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.
2. This REPORT consists of a total of 6 sheets, including this cover sheet.
 - ☒ This report is also accompanied by ANNEXES, i.e. sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

These annexes consist of a total of 5 sheets.

3. This report contains indications relating to the following items:

- I ☒ Basis of the report
- II ☐ Priority
- III ☐ Non-establishment of opinion with regard to novelty, inventive step and industrial applicability
- IV ☐ Lack of unity of invention
- V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- VI ☐ Certain documents cited
- VII ☐ Certain defects in the international application
- VIII ☐ Certain observations on the international application

Date of submission of the demand 09/03/2000	Date of completion of this report 05. 12. 00
Name and mailing address of the international preliminary examining authority:  European Patent Office D-80298 Munich Tel. +49 89 2399 - 0 Tx: 523656 epmu d Fax: +49 89 2399 - 4465	Authorized officer Huber, O Telephone No. +49 89 2399 8967 

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No. PCT/IT99/00262

I. Basis of the report

1. This report has been drawn on the basis of *(substitute sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to the report since they do not contain amendments (Rules 70.16 and 70.17).):*

Description, pages:

1,3-46	as originally filed	
2,2a	with telefax of	15/11/2000

Claims, No.:

1-12	with telefax of	15/11/2000
------	-----------------	------------

Drawings, sheets:

1/12-12/12	as originally filed
------------	---------------------

2. With regard to the **language**, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.

These elements were available or furnished to this Authority in the following language: , which is:

- ☐ the language of a translation furnished for the purposes of the international search (under Rule 23.1(b)).
- ☐ the language of publication of the international application (under Rule 48.3(b)).
- ☐ the language of a translation furnished for the purposes of international preliminary examination (under Rule 55.2 and/or 55.3).

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

- ☐ contained in the international application in written form.
- ☐ filed together with the international application in computer readable form.
- ☐ furnished subsequently to this Authority in written form.
- ☐ furnished subsequently to this Authority in computer readable form.
- ☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- ☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

4. The amendments have resulted in the cancellation of:

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No. PCT/IT99/00262

- ☐ the description, pages:
- ☐ the claims, Nos.:
- ☐ the drawings, sheets:

5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed (Rule 70.2(c)):

(Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.)

6. Additional observations, if necessary:

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. Statement

Novelty (N)	Yes:	Claims	1-12
	No:	Claims	
Inventive step (IS)	Yes:	Claims	
	No:	Claims	1-12
Industrial applicability (IA)	Yes:	Claims	1-12
	No:	Claims	

2. Citations and explanations
see separate sheet

Re Item V

Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. The document D1 was not cited in the international search report.

D1 = P. Rolin, L. Toutain and S. Gombault, 'Network Security Probe', Proceedings of the 2nd ACM Conference on Computer and communications security, pages 229-240, November 2-4, 1994, Fairfax, VA USA; <http://www.acm.org/pubs/citations/proceedings/commsec/191177/p229-rolin/>

2. Reference is further made to the following document:

D2 = EP-A-0 595 509 (LANNET DATA COMMUNICATIONS LTD) 4 May 1994 (1994-05-04)

3. **The subject-matter of Claim 1 of the present application cannot be considered as involving an inventive step (Article 33(3) PCT) for the following reasons.**

Document **D1**, which is considered to represent the most relevant state of the art, **discloses** (according to the wording of present claim) **the essential features of Claim 1**, a network access control device (page 232, right column, lines 7-8: "... a tool apart from the network routing components ..."; Figure 1: Security Analyser) through in series (page 233, right column, lines 21-24: "... upon their successive frames ...") deterministic recognition of application frames (page 232, right column, line 26: "NSP uses a passive taping (listener) method ...") satisfying a set of predetermined syntactical rules (Figure 2 Application column; page 233, right column, lines 21-24: "... upon their successive frames it can find elaborate information (application used, user name, ..."; page 233, right column, lines 45-47: "database of rules."; page 236, left column, lines 5-8: "a step in a transaction") which comprises:

- means for monitoring and interpretation of the application frames to recognize (page 232, left column, lines 47-48: "Since the NSP listen all message it is perfectly suitable to audit communication." and page 231, left column, lines 15-16: "This provides an opportunity to make elaborate multilayer control.");

- means for storing predetermined syntactical rules (page 232, right column, line 35: "... database that contains the security policy ..." and page 233, right column, lines 45-47: "... stored in a database of rules.");

- means for interpreting the predetermined rules (page 236, left column, lines 7-8: "The security policy defines the sequences to protect." and page 232, left column, last line- right column, line 2: "It should be easy to plug an audit interpreter module that looks for aggressions ...")

whereby the recognition is able to be performed on any frame component (page 233, right column, lines 12-14: "To be operational NSP needs only access to all the messages (Frames, packets, ...) that transit within the network."),

which further comprises forwarding means, for forwarding the application frame when recognized (as the "Network security probe (NSP)" in D1 runs in parallel to the communication on the LAN a forwarding is not necessary as the frame passes automatically; nevertheless the NSP would forward or allow forwarding the frames if attached to a proxy server or firewall as e.g. D2, column 2, lines 48-53) and return to sender means, for returning of the application frame when not recognized (page 235, left column, lines 7-20: "... send a frame within a connection established by any other station.").

The subject-matter of **Claim 1 differs therefrom only in** that the rules are compiled in a direct access data structure, which is stored and compared to the application frames which are recognized with said direct access data structure and the direct access data structure allows an access time substantially independent from the number of rules.

The **problem to be solved** by the present invention may therefore be regarded as how to improve the processing speed of a rule based analysing-system.

No positive contribution to inventive step can be seen in formulating this particular problem, because the need for quicker processing is essential for scaling applications to wider use.

The **solution** proposed in Claim 1 of the present application **cannot be considered as involving an inventive step** (Article 33(3) PCT) for the following reasons.

Claim 1 represents an obvious and consequently not inventive combination of features, as it is well known to the person skilled in the art, that compiling a code and executing it is quicker than interpreting the code. Therefore, the subject-matter of Claim 1 consists merely in the juxtaposition or association of known features (the protocol analyser and a compiler to achieve faster processing than an interpreter) functioning in their normal way and not producing any non-obvious working inter-relationship. The combined features do not mutually support each other in their effects to such an extent that a new technical result is achieved.

Claim 1 is therefore not inventive.

4. Dependent **Claims 2-12 do not contain** any features which, in combination with the features of any claim to which they refer, meet the requirements of the PCT (Article 33(3)) in respect of **an inventive step**, the reasons being as follows:

A person skilled in the art is aware of the following features which can be combined with the features of Claim 1 without producing a surprising effect:

- a. Converting rules into identifiers and compressing them (Claim 2) is commonly known.
- b. The returned application frame contains the reason of the failed forwarding (Claim 3) is a standard error handling technique.
- c. Rules are stores as objects (Claim 4) or pairs of data types (Claim 5) and combined with actions (Claim 7) is the general method for dealing with software data structures.
- d. Joker values (Claim 6) are commonly used to define default behaviour.
- e. A matricial structure for data (Claim 8) is also commonly employed to reduce storage size.
- f. The details of a control unit as in Claim 9 is shown in D1, Figure 4.
- g. Ordering of frames (Claim 9) to find the logical sequence of instructions (Claim 10) is known from D1, page 236, left column, lines 6-7.
- h. The control device is installed within the client machine (Claim 12) is also known from D1 (page 231, left column, lines 2-3).

Furthermore, in both types of devices of the known art there is the disadvantage that the recognition of the communication frames cannot be based on any frame component, but exclusively on frames at a non-application layer.

P. Rolin, L. Toutain and S. Gombault, 'Network Security Probe' discloses a device that provide a security service in a network environment that don't interject the security services into the operational sequences, rather, the security services are established as a parallel set of services. The major disadvantage of such a device is that use an optimistic approach: the device let pass all communications and checks in parallel for authorization, illegal communications will be stopped later. Another disadvantage is that the recognition is performed by a "pattern matching" method. This kind of methods are not error-free because are based on the comparison of the parts of the dialog with rules and patterns listed in a database and decided by security officers. Furthermore the performance of the security system depend both on the number of the rules to compare and on the their complexity, then is not possible to completely eliminate the risk that an illegal communication pass on the network.

The present invention overcomes such disadvantages of the prior art, as it provides a network access control device through in series deterministic recognition of application frames satisfying a set of predetermined syntactical rules comprising:

- means for monitoring and interpretation of the application frames to recognize;
- means for storing predetermined syntactical rules;
- means for compiling the predetermined syntactical rules in a direct access data structure;
- means for storing said direct access data structure; and
- means for comparing the application frames to be recognized with said direct access data structure,

whereby the recognition can be performed on any frame component and the direct access data structure allows an access time substantially independent from the number of rules,

characterized in that it further comprises forwarding means, for forwarding the application frame when recognized and return-to-sender means, for returning of the application frame when not recognized.

Preferably, the means for monitoring and interpretation of the application frames comprise:

- a) a data packets monitoring device at a layer corresponding to the OSI layer 2, said data packets comprising control frames and information frames, wherein the control and information frames contain a header portion and a body portion, said header portion allowing the distinction between an information frame and a control-

- 2 -

frame;

b) a control unit receiving as an input the data coming from the monitoring device and comprising means for the discrimination of the control frames from the information frames;

5 c) a dating unit connected to the control unit and associating a monitoring time to the control frames and to the information frames;

d) a discriminated data storing unit, storing the control and the information frames and the monitoring time thereof, bidirectionally connected to the control unit;

10 e) a predetermined data storing unit, bidirectionally connected to the control unit, said predetermined data representing possible interpretations of the information frames contained in the discriminated data storing unit;

f) means for comparing, by the control unit, said predetermined data stored in the storing unit with the data contained in the body portion of the

- 47 -

CLAIMS

1. A network access control device through in series deterministic recognition of application frames satisfying a set of predetermined syntactical rules comprising:

- means (205) for monitoring and interpretation of the application frames to recognize;
- means (201) for storing predetermined syntactical rules;
- means (202) for compiling the predetermined syntactical rules in a direct access data structure;
- means (203) for storing said direct access data structure; and
- means (204) for comparing the application frames to be recognized with said direct access data structure,

whereby the recognition can be performed on any frame component and the direct access data structure allows an access time substantially independent from the number of rules,

characterized in that it further comprises forwarding means, for forwarding the application frame when recognized and return-to-sender means, for returning of the application frame when not recognized.

2. The access control device according to claim 1, characterized in that said compiling means (202) of the predetermined syntactical rules comprise:

- conversion means, for converting the predetermined syntactical rules in a set of basic sequences of numerical identifiers; and
- compression means, for compressing the set of sequences thus obtained in a direct access data structure.

3. The access control device according to claim 1 or 2, characterized in that said return-to-sender means, for returning the application frames when not recognized, return information related to the reason of the failed forwarding.

4. The access control device according to any of the preceding claims, characterized in that the predetermined syntactical rules are stored as pairs of <object>/<action> fields.

5. The access control device according to claim 4, characterized in that the predetermined syntactical rules are stored as pairs of <data type>/<data value> fields.

- 48 -

6. The access control device according to claim 4 or 5, characterized in that the predetermined syntactical rules include one or more joker values.

7. The network access monitoring device according to claim 4, characterized in that the field <action> refers to the minimal set of commands

- Push

<value>

<variable>

<reading position>

10 <value at the reading position>

- Pop

<variable>

<reading position>

<at the reading position>

15 - And

- Mul

- Add

- Equal

- Next

20 - F_send_all

- F_dynamic.

8. The access control device according to claims 2 and 4, characterized in that the direct access data structure is represented through a matricial structure comprising object fields and action fields.

9. The access control device according to any of the preceding claims, characterized in that the means (205) for monitoring and interpretation of the application frames comprise:

30 a) a data packets monitoring device (9) at a layer corresponding to the OSI layer 2, said data packets comprising control frames and information frames, wherein the control and information frames contain a header portion and a body portion, said header portion allowing the distinction between an information frame and a control frame;

35 b) a control unit (15) receiving as an input the data coming from the monitoring device (9) and comprising means for the discrimination of the control frames from the information frames;

- 49 -

c) a dating unit (16) connected to the control unit (15) and associating a monitoring time to the control frames and to the information frames;

d) a discriminated data storing unit (17), storing the control and the information frames and the monitoring time thereof, bidirectionally connected to the control unit (15);

e) a predetermined data storing unit (18), bidirectionally connected to the control unit (15), said predetermined data representing possible interpretations of the information frames contained in the discriminated data storing unit (17);

f) means for comparing, by the control unit (15), said predetermined data stored in the storing unit (18) with the data contained in the body portion of the information frames stored in the discriminated data storing unit (17), thus reconstructing the information frames according to their specific application syntax;

g) means for ordering, according to the time and kind of communication, the information frames reconstructed according to their specific application syntax, thus reconstructing application sequences occurred between a determined source processor and a determined destination processor; and

h) means for ordering said information frames ordered according to the time and kind of communication also according to a logical criterion, thus reconstructing the logical path of said application sequences occurred between a determined source processor and a determined destination processor.

10. The access control device according to claim 9, characterized in that said means for ordering said information frames according to a logical criterion comprise means for reciprocally comparing the body portion of the information frames.

11. The access control device according to claim 9, characterized in that said means for ordering said information frames according to a logical criterion comprise means for comparing each sequence of body portions of the information frames with a set of predetermined sequences, said predetermined sequences representing possible interpretations of the information frames sequences contained in the discriminated data storing unit (17), said predetermined sequences being contained in said predetermined data storing unit (18).

12. The access control device according to any of the preceding claims, characterized in that it is implemented using a board installed on the processor on which the client applications operate.

M.H

PCTWORLD INTELLECTUAL PROPERTY ORGANIZATION
International Bureau

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification ⁷ : H04L 29/06, 12/26	A1	(11) International Publication Number: WO 00/10304 (43) International Publication Date: 24 February 2000 (24.02.00)
(21) International Application Number: PCT/IT99/00262 (22) International Filing Date: 11 August 1999 (11.08.99) (30) Priority Data: RM98A000542 12 August 1998 (12.08.98) IT (71) Applicant (for all designated States except US): ALASI DI ARCIERI FRANCO & C. S.A.S. [IT/IT]; Via Mario Chiri, 25, I-00171 Roma (IT). (72) Inventors; and (75) Inventors/Applicants (for US only): ARCIERI, Franco [IT/IT]; Via Mario Chiri, 25, I-00171 Roma (IT). MARINELLI, Guido, Maria [IT/IT]; Via Squillace, 108, I-00178 Roma (IT). TALAMO, Maurizio [IT/IT]; Via Emanuele Filiberto, 233, I-00185 Roma (IT). (74) Agents: STEINFL, Alessandro et al.; Società Italiana Brevetti S.p.A., Piazza di Pietra, 39, I-00186 Roma (IT).		(81) Designated States: AE, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, DE, DK, DM, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ZA, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SL, SZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG). Published <i>With international search report.</i> <i>Before the expiration of the time limit for amending the</i> <i>claims and to be republished in the event of the receipt of</i> <i>amendments.</i>
(54) Title: NETWORK ACCESS CONTROL DEVICE THROUGH FAST RECOGNITION OF APPLICATION FRAMES		
(57) Abstract <p>A network access control device for deterministic recognition of application frames satisfying a set of predetermined rules comprises: means (205) for monitoring and interpretation of the application frames to recognize; means (201) for storing the predetermined rules; means (202) for compiling the predetermined rules in a direct access data structure; means (203) for storing the direct access data structure; and means (204) for comparing the application frames to be recognized with the direct access data structure, wherein the recognition is able to be performed on any frame component and the direct access data structure allows an access time substantially independent from the number of rules.</p>		

FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece			TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA	Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	NZ	New Zealand		
CM	Cameroon			PL	Poland		
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakistan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
DE	Germany	LI	Liechtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singapore		

NETWORK ACCESS CONTROL DEVICE THROUGH FAST RECOGNITION OF APPLICATION FRAMES

5

DESCRIPTION

The present invention provides a network access control device through fast recognition of application frames satisfying a set of predetermined rules.

10 In particular, the device according to the invention allows both monitoring and interpretation of application protocols for network data transmission systems and the comparison with a set of control patterns of every monitored and interpreted communication frame. If a frame is recognized, the device allows access to the service. If the frame is not recognized, the device denies access to the service.

In the present description, for "pattern" (or access rule) the recognition statement of a particular communication frame will be intended.

15 Preferably, such statement will be intended as a set of <data type>/<data value> pairs assumed by the fields inside the communication frame. The <data type>/<data value> pairs are specified according to the various communication layers inside the communication frame concerning both the control and the information portion. In the present description, by way of example, communication frames of the HTTP (Internet browsing services) kind will be illustrated.

20 Network access control devices are known and can be divided into two large categories:

1) In a first category, the various access rules are represented by means of multidimensional matrices represented in a non-compressed form, using simple languages to access said matrices. The disadvantage of such a representation is given by the high memory occupation: a 10-dimensional matrix with 100 elements per dimension has a memory occupation of 100 10.

2) In a second category, the various access rules are represented by means of multidimensional matrices represented in a compressed form. The access to said matrices is not of a direct type. Such a manner has the disadvantage of requiring the use of high level languages, which determine the particular procedure to be activated in response to the recognition of an access rule by means of test and comparison operators. The particular control structures thus used burden the interpretation process, making it inefficient. However, the realization of generalised methods for information structure recognition on fast technologies (firmware) proves to be difficult, if not altogether impossible.

- 2 -

Furthermore, in both types of devices of the known art there is the disadvantage that the recognition of the communication frames cannot be based on any frame component, but exclusively on frames at a non-application layer.

The present invention overcomes such disadvantages of the prior art, as it provides a network access control device through deterministic recognition of application frames satisfying a set of predetermined rules comprising:

- means for monitoring and interpretation of the application frames to recognize;

- means for storing predetermined rules;

- means for compiling the predetermined rules in a direct access data structure;

- means for storing said direct access data structure; and

- means for comparing the application frames to be recognized with said direct access data structure,

wherein the recognition is able to be performed on any frame component and the direct access data structure allows an access time substantially independent from the number of rules.

Preferably, the means for monitoring and interpretation of the application frames comprise:

- a) a data packets monitoring device at a layer corresponding to the OSI layer 2, said data packets comprising control frames and information frames, wherein the control and information frames contain a header portion and a body portion, said header portion allowing the distinction between an information frame and a control frame;

- b) a control unit receiving as an input the data coming from the monitoring device and comprising means for the discrimination of the control frames from the information frames;

- c) a dating unit connected to the control unit and associating a monitoring time to the control frames and to the information frames;

- d) a discriminated data storing unit, storing the control and the information frames and the monitoring time thereof, bidirectionally connected to the control unit;

- e) a predetermined data storing unit, bidirectionally connected to the control unit, said predetermined data representing possible interpretations of the information frames contained in the discriminated data storing unit;

- f) means for comparing, by the control unit, said predetermined data stored in the storing unit with the data contained in the body portion of the

- 3 -

information frames stored in the discriminated data storing unit, thus reconstructing the information frames according to their specific application syntax;

g) means for ordering, according to the time and kind of communication, the information frames reconstructed according to their specific application syntax, thus reconstructing application sequences occurred between a determined source processor and a determined destination processor; and

h) means for ordering said information frames ordered according to the time and kind of communication also according to a logical criterion, thus reconstructing the logical path of said application sequences occurred between a determined source processor and a determined destination processor.

As it is known, a direct network access data structure allows the access to the i-th element without necessarily having to access to the preceding elements, as it occurs instead with sequential access data structures. Known examples of direct access data structures are vectors, matrices, correspondence tables, a memory of a processor etc.

A first advantage of the access control device according to the present invention is given by the flexibility wherewith a recognition pattern can be realized. In fact, by virtue of the use of the apparatus for monitoring and interpretation of application protocols, described in detail herebelow, the recognition of the communication frames can be based on any of the components of the frame, both on the control portion and on the information portion. Therefore, a recognition pattern can be realized (and therefore the access can be restricted) based on the contents of the exchanged information between client and server and not only based on the used network addresses and services.

A second advantage of the device according to the present invention is given by its capability to manage a very high number of patterns (in the order of millions) without any decay in the performances.

In fact, in a context where a high number of users, servers and application services on the same servers is involved, when it is desirable to directly manage (or to control and document) the accessibility of each user to the single server and to the application service thereby provided, the pattern number grows quadratically. For instance, given 1000 users on the territory and 100 servers of which it is desirable to manage and control the accesses, $1000 \cdot 100 = 100.000$ patterns are generated. This number further increases when it is desirable to manage and/or control the access to the application for each single server, the pattern number

- 4 -

growing to the order of the millions in the actual cases on of middle/big-dimensioned structures.

Such a pattern number is by all means acceptable for the device of the present invention.

5 In fact, the recognition of the acquired communication frames is based on a deterministic access algorithm (hence neither heuristic nor probabilistic) ensuring an access time that is constant and independent (under any input) from the pattern number.

10 Then the access control device performs for each correctly recognized frame the coordinating operation associated to recognition. As an example, once the recognition has occurred, the device will activate a TCP/IP layer (or layers corresponding to other protocols) communication with the server application individuated as result of the recognition, even a partial one, of the information component of the access frame, providing as parameters part of the already
15 recognized or yet unprocessed information component. The sending modes (parameter sending format, number of parameters to send, application to activate, etc.) are associated to the recognition action and are therefore stored in the patterns.

The access control device according to the present invention can be configured to operate both in positive logic and in negative logic.

20 In positive logic, all the frames that meet the recognition patterns will be considered as accepted and therefore brought to destination or are subjected to a coordinating, control and/or documentation action.

In negative logic, all the frames that do not meet the recognition patterns will be considered as accepted and therefore brought to destination or shall
25 be subjected to a coordinating, control and/or documentation action. All the recognized frames will not be brought to destination or shall not be subjected to a coordinating, control and/or documentation action.

The present invention will be illustrated herebelow by referring to a preferred embodiment thereof, explained by way of a non-limiting example.
30 Reference to figures of the annexed drawings will be made, wherein:

figure 1 shows a schematic diagram of the OSI standard;

figure 2 shows a schematic view of the type of data used on communication networks;

figure 3 shows a schematic view of the type of data used on
35 communication networks with reference to the TCP/IP protocol ;

- 5 -

figure 4 shows a block diagram of the apparatus for monitoring and interpretation belonging to the access control device according to the present invention;

5 figure 5 shows a flow chart explaining the operation of the component in figure 4;

figures 6 and 7 show additional flow charts for the understanding of what disclosed with reference to figure 5;

figures 8A and 8B show an example of application tree containing statistic information obtained by means of the component in figure 4;

10 figure 9 shows a block diagram of the access control device according to the present invention;

figures 10A and 10B show examples of the logical correspondence between bipartite graph and bidimensional matrix;

15 figure 11 contains an example of specification of predetermined rules; and

figure 12 shows a matricial representation of sequences of numerical identifiers.

20 Data transmission from a source device to a destination device can occur in different manners. However, to ensure a data exchange having the lowest possible chance of errors it is necessary to adopt a series of rules or control procedures. Said rules or procedures are known as "communication protocols".

A well known communication protocol is the "Open System Interconnection" (OSI) of the International Standards Organization (ISO). Said protocol is divided into seven layers, shown in figure 1. Layer 7 (application) on the source side contains information related to the sole message (M) to be sent to the destination side. The successive layers on the source side add control information to the message: layer 6 (presentation) divides the data of the original message into blocks (M1 and M2); layer 5 (session) adds a title (S) to indicate the sender, the receiver and some information related to the sequence; layer 4 (transport) adds information (T) related to the logic connection between the sender and the receiver; layer 3 (network) adds information related to the path (N) and divides the message into packets representing the standard communication unit in a network; layer 2 (data link) adds a title portion (B) and a tail portion (E) to the message to ensure the correct order of the various packets and to correct transmission errors; the single message bits and control information bits added by the various layers are transmitted on the physical medium through layer 1. The downward pointing arrow F1 on the

25

30

35

- 6 -

sender side indicates the manner according to which the outgoing message is constructed. Every addition to the message is verified and removed from the corresponding layer on the destination side. The upward pointing arrow F2 on the destination side indicates the manner according to which the incoming message is reconstructed.

With reference to the OSI standard, the communication unit in a network is the packet. Packets are in turn divided into frames. The beginning and the end of each frame are usually determined by delimitation characters. The frames are in turn divided into information and control frames. The information frames transport the data relative to the message that is to be transmitted throughout the network, while the control frames deal with the regulating modes of said transport, i.e. the flow control and the starting of the error recovery actions. Both the information and the control frames contain a header portion identifying the frame type and a body portion which is typical of the frame itself.

The information frame structure will be described with reference to figure 2. In the upper portion of said figure, the generic structure of a OSI layer 2 packet is schematically described, thus comprising both information frames 1 and control frames 2. A single information frame (OSI layer 3) is constituted by a header portion 3, containing the identification that the frame is an information frame, and by a body portion 4. The body portion (OSI layers 4-7) contains the real message 5, together with a plurality of fields 6, typical of the particular application syntax used, illustrated by way of example in the figure with the characters C1, C2 and C3. The application syntax is the information relative to the number of fields contained within the plurality 6, to the meaning of each of said fields and to the data contained therein.

The OSI model schematically described up to this point is just a conceptual model. A typical protocol normally adopted is for example the TCP/IP (Transmission Control Protocol and Internet Protocol). Said protocol, just like other communication protocols adopted, can be explained with reference to the layers structure of the OSI model. In fact, in each of said protocols, a certain source layer will divide the data it receives from an upper layer adding to said data a header and/or a tail and will forward all this to a lower layer. On the destination side the opposite operations will occur.

With reference to the following figure 3, a schematic view is shown of the type of data used on local communication networks with reference to the TCP/IP protocol carrying the HTTP application service (Internet browsing).

The Ethernet Layer substantially includes four kinds of fields:

- 7 -

- a destination network card address field 101;
- a source network card address field 102;
- a communication protocol field 103, in this case indicative of the carried IP protocol and of the length of the information portion; and
- 5 - an information field 104, i.e. containing the Ethernet layer data, i.e. the entire structure of the carried IP protocol.

The IP Layer (encapsulated in the Ethernet layer) substantially includes six types of fields:

- 10 - a series of control fields 105 identifying the version, the length, the transmission options, the filler etc.;
- a communication protocol field 106, in this case indicative of the TCP protocol;
- an IP destination address field 107, i.e. of the IP address of the packet receiver;
- 15 - an IP source address field 108, i.e. of the IP address of the packet sender; and
- an information field 109, i.e. containing all the IP layer data, i.e. the entire structure of the carried TCP protocol.

The TCP layer (encapsulated in the IP layer) includes four types of fields:

- 20 - a source port field 110, indicating the TCP service port used by the packet sender;
- a destination port field 111, indicating the TCP service port used by the packet receiver;
- a series of control fields 112 identifying the packet ID, the working window, 25 the crc, various options etc.; and
- an information field 113, i.e. containing the TCP layer data, i.e. the entire structure of the carried HTTP application service, i.e. the HTTP language commands and, in its information part, the HTML language commands.

30 Monitoring systems for the data transmitted between a sender node and a destination node are already known. However, said systems can only analyze the OSI layers 2 (data link) and 3 (network). The monitoring and the successive interpretation of the data at said layers allow only the monitoring of anomalies in the exchange protocol among the various components of a network data transmission system.

- 8 -

Therefore, a typical disadvantage of said prior art systems is their incapability of decoding the application piece of information transported on the network, i.e. the piece of information related to the layers 4-7 of the OSI standard.

In the following figures 4 to 8B, the structure and the operation of an apparatus for monitoring and interpretation of application protocols will be described in detail.

Reference will now be made to figure 4, showing a block diagram of the apparatus. First of all, in said figure a source node 7 and a destination node 8 are shown, terminals of the network portion in which the data are monitored and interpreted. Throughout the connection between said two nodes, schematically illustrated by arrows F3, F4, F5, F6 and by the transmission medium 23, data relative to plural communications between a first set of source processors (not shown in the figure) upstream of the source node 7 and a second set of destination processors (not shown in the figure) downstream of the destination node 8 travel bidirectionally.

Said data are monitored by means of a data monitoring device 9. Several are the monitoring devices known on the market; for instance, concerning networks based on Ethernet technology, the Fast Etherlink XL™ card produced by the company 3Com™ can be mentioned. As for networks based on X.25 technology, e.g. the S508 card produced by the Canadian company Sangoma™ can be mentioned. Such card can operate with different OSI layer 1 (physical layer) standards such as, for example the RS232 (or V.24) standard and the RS422 (or V.35) standard. The OSI layer 2 (data link) standards together with said card can operate are, for instance, the HDLC standard, or the X.25 standard, contained therein. Anyway, the kind of data monitoring device 9 to be selected for the purposes of the present invention can vary depending on which OSI layers 1 or 2 standards one needs to operate. In fact, it will be possible to use monitoring devices working with implementation standards different from the OSI layer 2, such as for example "Frame Relay" or SDLC or also BSC and the like. Said devices are well known to the person skilled in the art and will not be here described in detail.

The monitoring occurs "transparently" by means of two parallel connectors 10 and 11, schematically illustrated in the figure, allowing the monitoring of the data coming respectively from the source node 7 and from the destination node 8. The monitoring device 9, shown by the dashed block in the figure, includes a source data receiver 12, a destination data receiver 13 and a connection interface 14. The source data receiver 12 allows the reception of the data coming from the source node 7 only, as it is schematically indicated with the arrow F7; on the other hand, the

- 9 -

destination data receiver 13 allows the reception of the data coming from destination node 8 only as schematically indicated with the arrow F8. The data received in this manner are transmitted to the connection interface 14, as it is indicated by the arrows F9 and F10.

5 Each data packet situated at a layer corresponding to the OSI layer 2 read by the monitoring unit 9 is forwarded to a control unit 15, as indicated by arrow F11. The control unit 15 will be described in detail later. To each of said packets a reading time is associated by means of a dating unit 16, represented outside the control unit 15 for ease of description and therewith connected as indicated by arrow
10 F12. Such dating unit 16 can be any absolute time device on the market, in particular a radio or a satellite one. In a preferred embodiment of the present invention a radio controlled digital clock adjusted on the CET (Central European Time) broadcast by geostationary satellite was used.

15 Further to the association of the reading time by means of the dating unit 16, the control unit 15 discriminates the single frame so as to reconstruct the right logic/temporal forwarding sequence of the frames that, as it is known, does not always coincide with the received sequence: in fact, due to the routing techniques on telecommunications networks, it is possible for a forwarded sequence of the "ABC" type to be received in each of its possible permutations, i.e. "ABC", "ACB", "BAC",
20 "BCA", "CAB", "CBA". Therefore, the control unit 15 discriminates the information frames from the control frames. For example, if transmission of the information occurs in the HDLC format, the last bit of the header portion of the information frame is 0 whereas the last bit of the header portion of a control frame is 1. Therefore, inside the control unit 15 there are means, not described in the figure,
25 discriminating said last bit, e.g. a firmware contained in a ROM. In any case, no matter which data transmission code is used, the modes discriminating a control frame from a information frames will always be known. Therefore, it will always be possible to provide means for said discrimination. Such discrimination thus allows the storage of the single information frame deprived of the header portion and
30 comprising the body portion only, thus containing the information which is typical of the particular application syntax used, together with the message to be transmitted.

 The data incorporating the monitoring time and divided into information frames and control frames are stored inside a discriminated data storing unit 17, bidirectionally connected to the control unit 15 as indicated by arrow F13.
35 There is also a predetermined data storing unit 18, bidirectionally connected to the control unit 15. Said predetermined data represent possible interpretations of the

- 10 -

information or control frames contained in the discriminated data storing unit 17. Their use will be explained herebelow with reference to the following figures. The connection between the predetermined data storing unit 18 and the control unit 15 is indicated by arrow F14.

5 Reference will now be made to figure 5, showing a flow chart indicating the operations executed by the control unit 15 on the information frames stored in the discriminated data storing unit 17. The access to such information frame is intended to be selectively regulated by authorizations and privileges management systems such as passwords, encryption and decryption codes, badge readers and the like given to qualified users.

10 A first step S1 indicates the reading of the various packets by the monitoring unit 3. A second step S2 indicates the previously described discrimination operated by the control unit 15 between the information frames and the control frames, together with the association of the monitoring time.

15 On the non-application low layer control frames, whose use is marginal for the purposes of the present invention, a statistic processing might also be provided, operated in the step S3. Said processing is not described in detail at the moment; the modes by which it occurs will turn out to be clear at the end of the present description. The final result of such processing will provide a list of the control frames, reporting also the number of occurrences for each of said frames.

20 As for the information frames, the flow proceeds to a step S4 in which the single information frames are reconstructed according to their specific application syntax. To the purposes of said reconstruction, the application syntax structures of the single information frames must be known. In fact, they are contained inside the predetermined data storing unit 18 described with reference to the previous figure 3. Said unit 18 contains, for example in a text file, a formal abstract description for possible interpretations of the information or control frames. Said data represent the modes according to which the body portion of a single information frame can be structured, for example the machine transmission code (i.e. related to an information frame forwarded by the source or the destination), the number of the channel (i.e. related to a specific processor upstream of the source node or to a specific processor downstream of the destination node), protocol numbers, data processing numbers etc. Said unit 18 can of course contain the syntax of several application protocols of the information frames that are to be reconstructed in that moment.

25

30

35

- 11 -

A reconstruction of the information frames one by one is obtained by a sequential comparison of the body portion of each information frame with each one of the abstract models in the unit 18.

Further to this, the different application sequences occurred between a determined source processor and a determined destination processor can be reconstructed, i.e. ordered according to time and kind of communication. Throughout the present description, for application sequence will be intended the whole of the information frames exchanged between a determined source processor and a determined destination processor during a single communication. The application sequence ordered in step S5 will contain the single information frames ordered according to a time criterion only and not also to a logic one. Ordering by time will be possible through the time association occurred in the previous step S2.

To give also a logical ordering of the data inside a specific application sequence, the presence of a group of application rules directing the data exchange between source and destination can be useful, although not necessary. Said application rules, typical of the particular kind of conversation between a determined source processor and a determined destination processor, must be predetermined and as such, they as well are collected in the predetermined data storing unit 18. Said application rules are a series of possible interpretations of the information frames sequences contained in the discriminated data storing unit 17.

An example of such application rules is given by table 1 herebelow, wherein reference is made to a communication between a source representing a student (client) wanting to enroll to university via terminal, and a destination (server) representing the university where the student wants to enroll.

TABLE 1

1: AS ? FDB 15 AS ? FDB 5 AS ? FDB 0
The enrollment booking was regularly acquired
2: AS ? FDB 13 AS ? FDB 0
The client position is not regular
.....
.....
.....

Every row of said table is an application rule, indicating i.e. a possible data exchange application sequence between source and destination. The meaning of each application sequence is illustrated herebelow. For example, the first row indicates the following sequence of information frames:

- 12 -

- the source (AS) interrogates (?) the destination;
- the destination (FDB) answers with the activity number 15;
- the source (AS) interrogates (?) again the destination;
- the destination (FDB) answers with the activity number 5;
- 5 - the source (AS) interrogates (?) the destination; and
- the destination (FDB) answers with the activity number 0.

The result obtained at the end of this conversation is that the booking for the university enrollment is regularly acquired.

10 The structure of Table 1 is a mere example and it could also be illustrated with a tree structure having a number of branches depending on the number of application sequences provided. Every path down to one of the tree leaves would illustrate a particular application sequence, i.e. a particular conversation between source and destination, i.e. a particular information frame sequence between source and destination.

15 The number of application rules can be anyone. The larger the number of application rules provided, the bigger the chance to associate each of the application sequences temporally reconstructed in the step S5 with a well defined logic meaning, found by comparison with a particular application rule contained in the predetermined data storing unit 18 in figure 3. Therefore, in this manner it will be
20 possible to verify the correctness or the anomaly of the particular application sequence that is being compared in that moment.

In the step S6 in figure 5 the control unit 15 verifies first of all whether such application rules be available or less. Supposing that said application rules are known, the flow can proceed either toward a step S8 or toward a step S9,
25 depending on what was chosen in the step S7. The step S8 allows a simple classification of the application sequences. In fact, each application sequence is classified as belonging to a particular path among the various possible paths inside the application rules tree. The step S8 will be explained in greater detail with reference to the following figure 6.

30 On the other hand, in the step S9 the logical path of all the application sequences monitored by the apparatus in a predetermined time interval is reconstructed. Said step S9 will be described in greater detail with reference to the following figure 7.

35 The apparatus according to the present invention allows a reconstruction of the logical path of the application sequences also if a series of

- 13 -

application rules is not provided. In this event, the flow proceeds to a step S10, that will also be described later.

Reference will now be made to figure 6, which provides a more detailed explanation of what previously described with reference to step S8 of figure 5. In a first step S11 the single application sequence, object of the comparison, is selected. In a successive step S12, the elements which are characterizing for comparison purposes are selected inside the selected application sequence.

In the example of the enrollment to university previously described in table 1 said characterizing elements might be: the identification number of the source processor, the identification number of the user who required the enrollment operation, the data provided by the source and the data provided by the destination.

In the step S13 the characterizing elements of the considered application sequence are compared with one of the application rules of the above described table 1 searching for a possible correspondence. If such a correspondence is found, the flow proceeds to a step S14 wherein said correspondence is reported and will have to be taken into consideration in the results of the interpretation. Then the flow selects another sequence and executes again the step S11. If the correspondence at the step S13 is not found, the control unit 15 goes in step S15 to a subsequent rule and if (step S16) there are still rules allowing a comparison the control unit executes once again the comparison of step S13. If no further rules are found, the control unit reports an anomaly in the step S17. Such an anomaly might alternatively mean:

- either a kind of sequence which should not have occurred (a real anomaly);
- or
- a kind of sequence not inserted by mistake inside the application rules tree.

In each of said events, finding such an anomaly is certainly useful for the certification of the kinds of application sequences occurred in the network portion under examination.

Reference will now be made to the following figure 6 which gives a more detailed explanation of what described in the step S9 in figure 5.

The steps S18 and S19 select respectively the single application sequence and the characterizing elements of the same, similarly to what described with reference to the previous figure 5. The step S20 is to indicate the comparison between the application sequence and the preset application rules contained inside the predetermined data storing unit 18. If a correspondence is found, the flow proceeds to a step S21 wherein the correspondence found is taken into consideration

- 14 -

through the update of the related statistic fields. Steps S18-S20 will be subsequently repeated, until the end of the sequences to be classified. If no correspondence is found, the application sequence to be classified is new; it can be an anomaly or simply an unexpected sequence. In this event, the flow proceeds to a step S22 wherein the statistic fields related to that specific sequence are initialized. Furthermore, the new sequence will be inserted in the list of the preset sequences that are to be used for the comparison in the step S20. This is also indicated by the double pointing of the arrow F14 in the previous figure 4. Said particular sequences, i.e. the possible anomalies, can be evidenced in a particular manner to be recognized as such. Further to this, also in this case the steps S18-S20 are repeated until the end of the sequences to be classified. In particular, besides the number of crossings for each tree branch, it is also possible to monitor uncrossed branches.

In case there is no preset sequence of application rules, it will always be possible for the control unit to reconstruct the communication applications occurred in the network portion under control (step S9 in figure 5). In this event each analyzed application sequence will not be compared with the preset sequences, but with the previously analyzed sequences. Therefore, the tree structure containing statistic information will be reconstructed by reciprocal comparison of the body portion of the information frames. Also in this case, a tree will be constructed and it will be possible to know the number of crossings for each branch. Obviously, in this case it will not be possible to monitor the uncrossed branches as there will not be a prior knowledge of the existence of said branches.

Reference will now be made to figures 8A and 8B showing respectively an example of an information frame and an example of a tree structure containing statistic information obtained by means of the apparatus according to the present invention.

In figure 8A it is possible to notice four different fields: a first field 19 indicating the name of the source or destination processor; a second field 20 indicating the number of connections in the monitored time interval, a third field 21 indicating the average time length of each connection, counted for example in milliseconds, and a fourth field 22 indicating the code of the activity executed.

Figure 8B indicates the reconstructed tree. A first element E1 in the tree indicates that AS (source) connected 20 times, with an average connection time of 0 milliseconds (simple opening of the connection with the destination) and executed the activity with the code 0. A second element E2, E1's only "son", indicates that in all those 20 connections FDB (destination) answered with the

- 15 -

activity having the code 20, with an average connection time of 20 milliseconds. There were two manners of proceeding. AS answered for 18 times (element E3) with the activity 0 and twice (element E4) with the activity 1. The tree proceeds with other elements, whose meaning is now clarified by the context. The tree herewith disclosed
5 is the result of the logical ordering operated in the steps S9 or S10 in figure 5.

It is to be noted that the monitoring of the contents in the fields 19 and 22 of each element was operated in the step S4 in figure 5. The monitoring of the connections among the various elements, i.e. the fact that the element E2 is E1's "son" and that the elements E3 and E4 are E2's "sons" was operated either in the
10 step S9 or in the step S10 in figure 5.

The data flow relating to a particular application intercurrent between one or more determined processors upstream of a source node and one or more determined processors downstream of a destination node can be therefore reconstructed, in the sense of univocally determined in all its component parts. Therefore, what is
15 reconstructed is the conversation relating to one or more client/server applications. The logical reconstruction can take the form of the tree structure of figure 8B. Thus, communications relating to different applications (which therefore originate different application trees) can be reconstructed, and on the same source processor also more client-applications (relating to different server-applications) can be present. In the
20 same way, on a destination processor more server applications can be present.

Having ended the detailed description of an apparatus for monitoring and interpretation of network application protocols, herebelow the structure and the operation of the remaining components of the network access monitoring device according to the present invention will be described in detail.

25 The preferred connection mode of said device is a series connection, on Ethernet networks for 10 Mbits (connectors rj58 and rj45) and for 100 Mbits (rj45) or more.

The OSI layer 2 supported protocols will be all the protocols encapsulated in Ethernet, like 802.3, DOD IP, ARP etc.

30 The OSI layer 3 supported protocols will be all the protocols encapsulated in the various OSI layer 2 protocols, like TCP/IP, UDP/IP, Netbios/IEEE 802.3, SNA/IEEE 802.3 etc.

First of all, reference will be made to figure 9, showing a block diagram of the access control device according to the present invention. The various
35 blocks in figure 9 will be described herebelow one at a time.

Element 201:

- 16 -

It is the element storing the pattern recognition rules. The archive of the recognition rules is created reading a file or, e.g. directly typing in the rules through the keyboard.

5 Firstly, it should be assumed that said recognition rules are indicated as <data type>/<data value> pairs.

For instance, a recognition pattern of an Internet browsing request by a client with the address 192.23.40.1 to a web server of address 210.20.20.6 has the following structure:

10 (ETH_PROT, IP),
(IP_SRC_ADDR, 192.23.40.1),
(IP_DST_ADDR, 210.20.20.6),
(TCP_DST_PORT, HTTP)

wherein:

15 the first pair (ETH_PROT, IP) indicates that the protocol contained in the Ethernet layer must be the IP protocol;

the second pair (IP_SRC_ADDR, 192.23.40.1) indicates that the IP address of the packet sender must be the one indicated;

the third pair (IP_DST_ADDR, 210.20.20.6) indicates that the IP address of the packet receiver must be the one indicated; and

20 the fourth pair (TCP_DST_PORT, HTTP) indicates that the TCP service used is the HTTP (web) one.

The identification numbers on the right of the pairs can also assume values that are not predetermined, for instance if it is desirable to identify all the addresses of a subnetwork. In this case the address of the previous example can be
25 expressed as 210.20.20.* where the symbol * (asterisk) indicates a joker value, i.e. all the possible values that can be in that position. In the same pair two or more asterisks may appear: e.g., 210.*.20.*, thus indicating a set of 65536 (or more) different addresses. Other accepted configurations are e.g.: 2*.20.20.* indicating all the addresses beginning with 2 and ending with a subaddress comprised between 0
30 and 255 (in this case a total of $100 \times 256 = 25600$ different addresses).

A further example of a recognition pattern for the IBM NetBios protocol between two processors is the following:

(ETH_PROT, IEEE802),
(IEEE802_DST_SAP, IBM_NETBIOS)

- 17 -

When wishing to force the recognition of the network cards involved in the NetBios communication (6 bytes, including the card issuer code and the card number), the pattern becomes:

5 (ETH_SRC_ADDR, 0xFF45DE782201),
 (ETH_DST_ADDR, 0xF237C811000F),
 (ETH_PROT, IEEE802),
 (IEEE802_DST_SAP, IBM_NETBIOS).

Element 202:

10 It is the pattern compiler, consisting of a conversion element for converting the rules contained in 201 into a set of sequences of numerical identifiers and consisting of a compression element for compressing the identifiers thus obtained.

i) Conversion element

15 The recognition rules appearing as <data type>/<data value> pairs are converted into sequences of numerical identifiers, constituting the basis for the recognition of the frames read from the network.

For instance, given the rule

(ETH_PROT, IP),
 (IP_SRC_ADDR, 228.186.33.90),
 20 (IP_DST_ADDR, 41.240.227.149),
 (TCP_DST_PORT, HTTP)

it follows that:

a) the first pair (ETH_PROT, IP) is converted into two hexadecimal data pairs (in which the 0x prefix indicates that the subsequent value is represented in hexadecimal):
 25

0x0C 0x0800

0x49 0x06

wherein:

- the first row contains two values, 0C and 0800. The digit farther left of the first value (0) identifies an Ethernet frame. The second digit of the first value (C) indicates the position inside the frame (13th byte, considering the first one to be in position 0). The second value (0800) is the identification code of the IP protocol when contained in an Ethernet frame; and
 30

- the second row contains two values, 49 and 06. The digit farther left of the second value (4) identifies an IP net. The second digit of the first value (9) indicates
 35

- 18 -

the position inside the net. The second value (06) identifies the TCP protocol contained in IP.

b) the second pair (IP_SRC_ADDR, 228.186.33.90) is converted into four hexadecimal data pairs:

5 0x4C 0xe4
 0x4D 0xba
 0x4E 0x21
 0x4F 0x5a

10 wherein each pair indicates respectively the IP frame(4), the position (from C to F) and the value of each single element constituting the source address: in fact e4 in hexadecimal corresponds to 228 in decimal, ba in hexadecimal corresponds to 186 in decimal, 21 in hexadecimal corresponds to 33 in decimal and 5a in hexadecimal corresponds to 90 in decimal.

15 c) the third pair (IP_DST_ADDR, 41.240.227.149) is converted into four hexadecimal data pairs:

 0x410 0x29
 0x411 0xF0
 0x412 0xE3
 0x413 0x95

20 wherein each pair indicates respectively the IP frame(4), the position (from 10 to 13) and the value of each single element constituting the destination address: in fact 29 in hexadecimal corresponds to 41 in decimal, F0 in hexadecimal corresponds to 240 in decimal, E3 in hexadecimal corresponds to 227 in decimal and 95 in hexadecimal corresponds to 149 in decimal.

25 d) the fourth pair (TCP_DST_PORT, HTTP) is converted into a pair of hexadecimal data:

 0x82 0x0080

30 in which the digit farther left of the first value (8) indicates the TCP frame, the second digit of the first value (2) indicates the position inside said frame (the third starting from zero) whereas the second value 0080 indicates the HTTP service (the one used by web applications).

 Therefore, starting from rule

 (ETH_PROT, IP),
 (IP_SRC_ADDR, 228.186.33.90),
35 (IP_DST_ADDR, 41.240.227.149),
 (TCP_DST_PORT, HTTP)

- 19 -

the sequence

0x0C 0x0800, 0x49 0x06, 0x4C 0xe4, 0x4D 0xba, 0x4E 0x21, 0x4F 0x5a,
0x410 0x29, 0x411 0xf0, 0x412 0xe3, 0x413 0x95, 0x82 0x0080

is obtained.

5 It is intended that all the conversions hereto described are made possible through a sequential comparison of each of the <data type>/<data value> pairs with a table storing all possible <data type>/<data value> pairs together with the corresponding hexadecimal data pair.

10 Actually, a more extended form can be used for the rules thus defined, capable of being semantically represented by the <object>/<action> pair. The <object> field indicates the set of properties (including the value) assumed by the element currently under examination, whereas the <action> field expresses the actions that are to be executed after having recognized said object in the communication frame.

15 For instance, in the hexadecimal pairs of the <data type>/<data value> kind it is apparent how the <data type> field contains a double information, i.e. both the protocol (or the frame type) to which reference is made, and the position inside said protocol.

20 In the event of complex application protocols, the monitored frames are usually represented by means of a language of the LL(1) type (i.e., according to the definition of Chomsky, a language having no control structures and with no limitations for the definition of the interpretation processes of the information structures). In this event, the <action> field will make reference to a minimal set of basic instructions reported herebelow:

25 - **Push**
 <value>
 <variable>
 <reading position>
 <value at the reading position>
30 - **Pop**
 <variable>
 <reading position>
 <in the reading position>
 - **And**
35 - **Mul**
 - **Add**

- 20 -

- Equal
- Next
- F_send_all
- F_dynamic

5

Herebelow a schematic outline of the meaning of said basic instructions is provided for sake of completeness.

- Push <value> inserts a value in the stack dedicated to the recognition process under way, for instance: PUSH(35), the value 35 is inserted in the stack;

10 - Push <variable> inserts the content of a variable in the stack dedicated to the recognition process under way, for instance: PUSH(v12), if the value of the "v12" variable is 8, then 8 is inserted in the stack;

15 - Push <reading position> inserts in the stack dedicated to the recognition process under way the position of the value currently read in the input stream, for instance PUSH(pos) if the value of pos, a variable indicating the reading position, is 5, then 5 is inserted in the stack;

20 - Push <value at the reading position> inserts the value read in the input stream under recognition in the "reading position" in the stack dedicated to the recognition process under way, e.g. PUSH(v_pos), if the value of pos, a variable indicating the reading position, is 5 and if at position 5 of the input stream there is the value 30, then 30 is inserted in the stack;

25 - Pop <variable> inserts the stack head in the "variable" variable e.g. POP(v3), if the value 10 was inserted in the stack head, meaning that the last operation performed with the stack was e.g. push(10), then the value 10 goes into the "v3" variable;

 - Pop <reading position> inserts the stack head in the variable indicating the successive position to be read in the input stream, e.g. POP(pos), if in the stack head the value 10 has been inserted, then the next element that will be read by the input stream will be the one in position 10;

30 - Pop <in the reading position> inserts the stack head in the position indicated by the variable indicating the next position to be read in the input stream, e.g. POP(v_pos), if the value 10 has been inserted in the stack head, the value of the next element that will be read by the input stream will be 10;

35 - And, Mul, Add, Or, Sub are all logical and arithmetical operations. The operation is performed on the values contained in the first two stack positions, the result becomes the stack head and the two used values are removed from the stack;

- 21 -

example: the logical arithmetical operations follow the reversed Polish notation (RPN). It is now supposed to have to execute the operation $10*30$ to be executed: the entailed program will be:

```

5      PUSH(10)
      PUSH(30)
      MUL

```

now, in the stack head there is $300=30*10$.

- Equal <value>, Equal <variable>, Equal <reading position>, Equal <value at the reading position> verifies whether in the stack head there is a value equal to the one forwarded as a parameter. The result (0 if different, 1 if equal) is inserted in the stack head;

- f_send_all is a function that, when operated, reports the entire input stream to the output;

- Next <value>, Next <variable> increments of the value contained in "value" or of the value contained in "variable" the variable indicating the input stream position from which the next value is to be read; lastly

- f_dynamic("name") operates the "name" function connected to the coordinating element through dynamic connection mechanisms (as DLL in Windows or shared_libraries in UNIX, or RPC/DCE mechanisms, ...) forwarding thereto the values contained in the stack as parameters.

A possible implementation syntax (adopted from C language) of the set of the <item>/<action> pairs can be the following one:

```

      typedef struct _item {
                unsigned char object;
25      unsigned long int action;
      } Item;

```

```

      typedef struct _record {
                int num_of_items;
30      Item * items;
      } Record;

```

Record * input_second_step;

35 wherein:

- 22 -

- the "object" field is expressed as a single byte ("unsigned char"). Such a choice does not entail limitations, since an entire value (2 to 4 bytes long) can be considered as a sequence of bytes and therefore it can be processed one byte at the time; and

5 - the field "action" is expressed as "unsigned long int". Hence, it can represent both a number (compatible with the first notation) and a pointer to a structure or to a set of functions (compatible with the second notation).

10 Usually the number of different sequences is very high. By way of example, taking into consideration exclusively the TCP-IP protocol, for a relatively low number of 1000 "clients" (i.e. of processors using application services made available by other processors) and of 10 "servers" (i.e. of processors providing application services to the clients) and of an average of 10 application services per "server" (as e.g. FTP, TELNET, HTTP, MAIL, NFS, TIME, DNS), in order to discriminate all the possible "pairings" among client-server-service, rules indicating
15 1000*10*10=100000 different pattern sequences in the communication frames have to be determined.

20 This number, already well above the dimension deemed acceptable for the internal addressing tables of the routers and of the commercial firewalls, increases very rapidly when rules operating not merely at the level of a control portion of the communication protocols, but operating on the level of the data portion as well are determined, as is the case in the present invention.

25 The above defined language of rules allows to write rules allowing the identification of elements of the data portion of the communication protocol: in fact, if not merely the "identification" of a "client" is desirable, but also when he tries to access a specific WEB page from a network (which is possible by means of the present invention), it is not enough to operate at a level of the communication protocol control portion (only the fact that a command was sent at the level of an HTTP service would be recognized) being it necessary instead to operate at a level of the TCP-IP protocol data portion in order to identify the particular string determining
30 access to the WEB page requested by the client.

 In Annex A a second example of language is reported.

ii) Compression element of the set of sequences obtained in a direct access data structure

35 Said second element of the pattern compiler 202 allows a construction of the compression data structure ensuring a constant access time (i.e., regardless of

- 23 -

the number of sequences) and an optimal memory occupation (i.e., equal to the amount of memory required to store sequences in a non structured way multiplied for a constant value) for recognition of the sequences stored in said structure in the communication frames that are readable from a network. Moreover it is possible to
5 update such a data structure in a number of steps proportional to $N \cdot \log(N)$, where N is the number of new sequences to be inserted.

In particular, reference will be made to the articles:

a) "Time Optimal Digraph Browsing on a Sparse Representation",
Mathematics Department Tech. Report, Tor Vergata University of Rome 8/97, 1997
10 by M. Talamo and P. Vocca;

b) "Optimal Bounds on Complexity of Sparse Partial Orders", Mathematics
Department Tech. Report, Tor Vergata University of Rome, 9/97, 1997 by M.
Talamo and P. Vocca;

c) "Optimal Digraph Search on a Compressed Representation", Mathematics
15 Department Tech. Report, Tor Vergata University of Rome, 11/98, 1998 by M.
Talamo and P. Vocca; and

d) "Compact Implicit Representation of Graphs", WG98 proceedings, June
1998 by M. Talamo and P. Vocca.

In said articles data structures allowing a constant time access, i.e.
20 regardless of the number of data represented by them, are described.

The algorithm for obtaining said data structures is applied to access
structures of the "bipartite graph" kind, e.g. as the one represented in figure 10A. In
such a graph the nodes can be separated into two separate subgroups (from A to E
and from 0 to 4 in figure), in such a way that each node belonging to a first subset
25 can be connected only with nodes belonging to the second subset and vice versa.
With reference to figure 10A, node A is connected with node 0 and node 2, node B is
connected with node 0 and node 2, node C is connected with node 1 and node 4,
node D is connected with node 3, and node E is connected with node 3.

Such connections can be expressed by means of a bidimensional
30 matrix of the kind reported in figure 10B, where with the symbol x the connections
active between lines and columns have been represented. Therefore, it can be
concluded that the bipartite graphs are equivalent to the bidimensional matrices and
that therefore the constant time accessibility results obtained with reference to the
above cited article can also apply to structures such as bidimensional matrices.

- 24 -

Therefore, the compression element will compress the sequences obtained through the conversion element, and will generate a variety of bidimensional matrices indicating such sequences.

* * *

5 The algorithm by which the compression element operates, described herebelow, (from STEP 1 to STEP 11) is intended to be implemented in any suitable programming language (e.g. in C language) and stored in a ROM.

The input to the algorithm consists in the sequence of numerical identifiers (records) of a preset variable length.

10 By way of example, together with the various algorithm steps a complete compilation cycle for a specific practical case will be reported, in order to fully describe the operation manners of the algorithm itself. Accordingly, reference to communication structures of the Ethernet kind will be made again. Obviously, the operation of the control device according to the present invention remains unaltered
15 even in the event the apparatus for monitoring and interpretation does not provide Ethernet frames monitored on the network, but directly provides instead TCP/IP communications or anyhow very long data streams.

STEP 1 (specification of predetermined rules, see also figure 11):

20 It is supposed to have to manage and coordinate Ethernet communication frames by means of the following connection diagrams:

connection a) 132.147.200.10 can connect with 132.147.160.1 only for the service:

- WWW, service TCP 80.

25 connection b) 132.147.200.10 can connect with 132.147.160.2 for the services only:

- SMTP, service TCP 25;

- NETBIOS, services TCP 137, 138 and 139.

connection c) 132.147.200.20 can connect with 132.147.160.1 only for the services:

30 - FTP, services TCP 20 and 21;

- TELNET, service TCP 23.

connection d) 132.147.200.20 can connect with 132.147.160.2 only for the services:

- SMTP, service TCP 25;

35 - WWW, service TCP 80.

- 25 -

connection e) 132.147.200.20 can connect with 132.147.160.3 only for the services:

- WWW, service TCP 80;
- SNMP, services TCP 161 and 162;
- 5 - NFS, service TCP 2049;
- TELNET, service TCP 23.

Further, all the communications of the ARP (Ethernet layer protocol) and ICMP (IP-layer protocol) kind will have to be accepted.

10 STEP 2 (conversion of rules in a set of sequences):

A set of 17 records (in which each record consists of a set of <item>/<action> pairs) is obtained based on said connection diagram. In particular, record 1 represents connection a), records 2 to 5 represent connection b), records 6 to 8 represent connection c), records 9 to 10 represent connection d), records 11 to 15 represent
15 connection e), record 16 represents the Ethernet ARP protocol, and lastly record 17 represents the ICMP protocol in IP.

Connection a)

RECORD 1

20	0x08, 0x000C	
	0x00, 0x000D	IP protocol in Ethernet
	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
25	0xC8, 0x400E	
	0x0A, 0x400F	132.147.200.10
	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
30	0x01, 0x4013	132.147.160.1
	0x00, 0x8002	
	0x50, 0x8003	WWW 80

Connection b)

35 RECORD 2
0x08, 0x000C

- 26 -

	0x00, 0x000D	IP protocol in Ethernet
	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
5	0xC8, 0x400E	
	0x0A, 0x400F	132.147.200.10
	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
10	0x02, 0x4013	132.147.160.2
	0x00, 0x8002	
	0x19, 0x8003	SMTP 25
	<u>RECORD 3</u>	
15	0x08, 0x000C	
	0x00, 0x000D	IP protocol in Ethernet
	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
20	0xC8, 0x400E	
	0x0A, 0x400F	132.147.200.10
	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
25	0x02, 0x4013	132.147.160.2
	0x00, 0x8002	
	0x89, 0x8003	NETBIOS 137
	<u>RECORD 4</u>	
30	0x08, 0x000C	
	0x00, 0x000D	IP protocol in Ethernet
	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
35	0xC8, 0x400E	
	0x0A, 0x400F	132.147.200.10

- 27 -

	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
	0x02, 0x4013	132.147.160.2
5	0x00, 0x8002	
	0x8A, 0x8003	NETBIOS 138

RECORD 5

	0x08, 0x000C	
10	0x00, 0x000D	IP protocol in Ethernet
	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
	0xC8, 0x400E	
15	0x0A, 0x400F	132.147.200.10
	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
	0x02, 0x4013	132.147.160.2
20	0x00, 0x8002	
	0x8B, 0x8003	NETBIOS 139

Connection c)

RECORD 6

25	0x08, 0x000C	
	0x00, 0x000D	IP protocol in Ethernet
	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
30	0xC8, 0x400E	
	0x14, 0x400F	132.147.200.20
	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
35	0x01, 0x4013	132.147.160.1
	0x00, 0x8002	

- 28 -

0x14, 0x8003

FTP 20

RECORD 7

0x08, 0x000C

5

0x00, 0x000D

IP protocol in Ethernet

0x06, 0x4009

TCP protocol in IP

0x84, 0x400C

0x93, 0x400D

0xC8, 0x400E

10

0x14, 0x400F

132.147.200.20

0x84, 0x4010

0x93, 0x4011

0xA0, 0x4012

0x01, 0x4013

132.147.160.1

15

0x00, 0x8002

0x15, 0x8003

FTP 21

RECORD 8

0x08, 0x000C

20

0x00, 0x000D

IP protocol in Ethernet

0x06, 0x4009

TCP protocol in IP

0x84, 0x400C

0x93, 0x400D

0xC8, 0x400E

25

0x14, 0x400F

132.147.200.20

0x84, 0x4010

0x93, 0x4011

0xA0, 0x4012

0x01, 0x4013

132.147.160.1

30

0x00, 0x8002

0x17, 0x8003

TELNET 23

Connection d)

RECORD 9

35

0x08, 0x000C

0x00, 0x000D

IP protocol in Ethernet

- 29 -

	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
	0xC8, 0x400E	
5	0x14, 0x400F	132.147.200.20
	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
	0x02, 0x4013	132.147.160.2
10	0x00, 0x8002	
	0x19, 0x8003	SMTP 25
	<u>RECORD 10</u>	
	0x08, 0x000C	
15	0x00, 0x000D	IP protocol in Ethernet
	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
	0xC8, 0x400E	
20	0x14, 0x400F	132.147.200.20
	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
	0x02, 0x4013	132.147.160.2
25	0x00, 0x8002	
	0x50, 0x8003	WWW 80
	Connection e)	
	<u>RECORD 11</u>	
30	0x08, 0x000C	
	0x00, 0x000D	Ethernet IP protocol
	0x06, 0x4009	TCP/IP protocol
	0x84, 0x400C	
	0x93, 0x400D	
35	0xC8, 0x400E	
	0x14, 0x400F	132.147.200.20

- 30 -

	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
	0x03, 0x4013	132.147.160.3
5	0x00, 0x8002	
	0x50, 0x8003	WWW 80
 <u>RECORD 12</u>		
	0x08, 0x000C	
10	0x00, 0x000D	IP protocol in Ethernet
	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
	0xC8, 0x400E	
15	0x14, 0x400F	132.147.200.20
	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
	0x03, 0x4013	132.147.160.3
20	0x00, 0x8002	
	0xA1, 0x8003	SNMP 161
 <u>RECORD 13</u>		
	0x08, 0x000C	
25	0x00, 0x000D	IP protocol in Ethernet
	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
	0xC8, 0x400E	
30	0x14, 0x400F	132.147.200.20
	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
	0x03, 0x4013	132.147.160.3
35	0x00, 0x8002	
	0xA2, 0x8003	SNMP 162

- 31 -

RECORD 14

	0x08, 0x000C	
	0x00, 0x000D	IP protocol in Ethernet
5	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
	0xC8, 0x400E	
	0x14, 0x400F	132.147.200.20
10	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
	0x03, 0x4013	132.147.160.3
	0x08, 0x8002	
15	0x01, 0x8003	NFS 2049

RECORD 15

	0x08, 0x000C	
	0x00, 0x000D	IP protocol in Ethernet
20	0x06, 0x4009	TCP protocol in IP
	0x84, 0x400C	
	0x93, 0x400D	
	0xC8, 0x400E	
	0x14, 0x400F	132.147.200.20
25	0x84, 0x4010	
	0x93, 0x4011	
	0xA0, 0x4012	
	0x03, 0x4013	132.147.160.3
	0x00, 0x8002	
30	0x17, 0x8003	TELNET 23

and lastly

RECORD 16

	0x08, 0x000C	
35	0x06, 0x000D	ARP protocol in Ethernet

- 32 -

RECORD 17

0x08, 0x000C

0x00, 0x000D

0x01, 0x4009

IP protocol in Ethernet

ICMP protocol in IP

5

The structure thus obtained can be expressed in a matricial form, according to the representation in figure 12. It is to be noted that the various records can have different lengths. In fact, there are 15 records of length 13, 1 record of length 2 and 1 record of length 3.

10

STEP 3:

Set CONT = 0

STEP 4:

15

Column 0 and column CONT of the above reported sequence are taken, and a new sequence of records containing only 2 items (the one in column 0 and the one in column CONT) is created.

STEP 5:

20

Doubles are eliminated from this new sequence of records.

STEP 6:

Set ROW=0

25

STEP 7:

A weighted bipartite graph is created with the new record sequence, by inserting for each record:

- the value of the item in position 0 (upper node id);
- the value of the item in position CONT (lower node id);
- the action of the item in position CONT (as the first weight of the arc between the two nodes);
- ROW (as the second weight of the arc between the two nodes).

30

Further, for each pair of inserted nodes, the item value in the position 0 in the original record sequence is replaced with the new ROW value, and then ROW=ROW+1 is set.

35

- 33 -

STEP 8:

The bipartite graph thus obtained is converted into a bidimensional matrix and a vector by means of the basic algorithm of which at the above mentioned articles. Note however that the algorithm described herewith constitutes an extension of said basic algorithm, in particular concerning the previous step 7.

STEP 9:

The bidimensional matrix and the vector are stored.

10 STEP 10:

Set CONT=CONT+1

STEP 11:

15 If CONT is not equal to the maximum number of items of the records the step 4 is repeated, else the algorithm is ended.

* * *

The sequence of bidimensional matrices and vectors constitutes the compressed data structure that will be used for recognition of the input streams. Such structure is accessible in a direct manner.

20 Herebelow again reference to figure 9 will be made.

Element 203 (memory containing the compressed patterns):

25 Such element consists of the sequence of matrices resulting from the above mentioned compression algorithm. By virtue of the high compression rate of said algorithm, the dimension of this sequence of matrices is directly proportional to the number of active connections of the original matrix, being therefore directly storable in the central memory. In case of a high number of active connections (>100.000.000), said sequence of compressed matrices can be managed by means of mass storage devices.

Element 204 (pattern recognizer):

30 Such element allows the comparison between the application frames to be recognized, monitored by means of the element 205 and the direct access data structure stored in 203.

35 The element 204 is realized in a microchip, and it substantially consists of a software implementing a direct accessing technique on matrices, in order to access the matrices stored in 203.

- 34 -

Therefore, the acceptability or non acceptability of the frame read from the network can be recognized in a completely deterministic way.

* * *

5 In order to provide a detailed example of the operation of said recognizer, herebelow first of all the structure of the matrices stored in 203 is reported, using a syntax similar to that of the C language:

```

//Structure for a bidimensional Matrix and a vector
typedef struct _matrices_AB {
    unsigned long int row_a;    //Number of rows of the matrix
10    unsigned long int col_a;    //Number of columns of the matrix
    unsigned long int col_b;    //Number of elements of the vector
    unsigned long int **mA;    //Matrix of Values
    Action ***mP;              //Matrix of Actions
    unsigned long int *mB;    //Vector
15    } mat_AB;

typedef struct _vec_matrices_AB {
    mat_AB * MAB;              //Set of matrices and vectors
    unsigned long int num_mab; //Number of matrices and vectors
20    } * Vec_mat_AB;
```

Five input records and the resulting matrices are reported herebelow. In such example the description of the records is performed by means of the <item>/<action> syntax hereto reported. The associated actions are extremely
25 simplified (a single action per each recognition). Moreover, for sake of simplicity, the recognition is assumed to begin always from the first byte of the input stream.

```

RECORD 1
0x01 next(1)
30 0x03 next(1)
    0x02 f_send_all
```

```

RECORD 2
0x01 next(1)
35 0x06 next(1)
    0x04 f_send_all
```

- 35 -

RECORD 3

0x02 next(1)

0x07 next(1)

0x03 f_send_all

5

RECORD 4

0x01 next(1)

0x02 f_send_all

10

RECORD 5

0x05 next(1)

0x01 f_send_all

15

For next(1) the action of positioning on the successive byte in the data stream is intended. For f_send_all the action of forwarding of to the outside all the data stream is intended.

By means of the aforescribed algorithm the following matricial structure is obtained:

- 36 -

1	MATRIX OF VALUES 0: [X] 1: [0] 2: [1] 3: [X] 4: [X] 5: [2]	MATRIX OF ACTIONS (1, 0) NEXT(1) (2, 0) NEXT(1) (5, 0) NEXT(1)	VECTOR B X 0 0 X X 0
2	MATRIX OF VALUES 0: [X] 1: [4] 2: [0] 3: [1] 4: [X] 5: [X] 6: [2] 7: [3]	MATRIX OF ACTIONS (1, 0) F_SEND_ALL (2, 0) F_SEND_ALL (3, 0) NEXT(1) (6, 0) NEXT(1) (7, 0) NEXT(1)	VECTOR B 0 0 0
3	MATRIX OF VALUES 0: [0 4] 1: [X X] 2: [1 X] 3: [3 X] 4: [2 X]	MATRIX OF ACTIONS (2, 0) F_SEND_ALL (3, 0) F_SEND_ALL (4, 0) F_SEND_ALL	VECTOR B 0 0 0 0 1

In order not to overburden the present description, the various steps from the records to the graphically described matricial structure (after all, simple applications of the above described algorithm) will not here be described in detail. Moreover, for sake of clarity the matrix of values has been represented as physically separated from the matrix of actions.

5

Instead, the comparison steps that are performed in order to recognize or not the monitored data streams will be described in detail. Said steps relate to the specific case of matricial structure hereto described.

- 37 -

1) EXAMPLE OF RECOGNITION IN THE EVENT THE STREAM IS
IDENTICAL TO THE RECORD 1: 0x01 0x03 0x02

First read value is 01.

Being in an initial condition, it is used as an index of the matrix as
5 well as of the vector.

The adopted Matrix/Vector pair is in the position 1 of the above
reported list.

The row index of matrix A is determined by the element which has
been read, i.e. Row A =01, i.e. the first row.

10 The column index of matrix A is determined by the value contained
by vector B at the position corresponding to the element which has been read, i.e.
Column A =B[0x01]=0, i.e. the 0-th column.

Therefore, the value reported in A[1, 0], i.e. 0 will be read. Said value
is the successive index of vector B.

15 Next, the action reported in A [1, 0], i.e. the numeric value
corresponding to the action next(1) will be read.

Therefore the aforesaid action will be executed, thus proceeding to the
successive data stream value.

20 The successive value will be reached, using then the Matrix/Vector
pair at position 2 of the above reported list.

Read value is 03.

The row index of Matrix A is determined by the element which has
been read, i.e. Row A =03, i.e. the third row.

25 The column index of matrix A is determined by the value contained in
vector B at the position corresponding to the value reported in A[1, 0] obtained in the
previous step (i.e. 0). Column A =B[0]=0, i.e. the 0-th column.

Therefore, the value reported in A[3, 0] i.e. 1 will be read. Such value
is the next index of vector B.

30 Then the action reported in A[3, 0], i.e. the numeric value
corresponding to the action next(1) will be read.

Therefore, the aforesaid action will be executed, and the position shall
be shifted to the next value of the data stream.

The subsequent value will be reached and the Matrix/Vector pair at
position 3 of the above reported list will be used.

35 Read value is 02.

- 38 -

The row index of matrix A is determined by the element which has been read, i.e. Row A =02, i.e. the second row.

The column index of matrix A is determined by the value contained in vector B at the position corresponding to the value reported in A[3, 0] obtained in the previous step (i.e. 1). Column A =B[1]=0, i.e. the 0-th column.

Therefore, the value reported in A[2, 0], i.e. 1, will be read. Such value is the successive index of vector B.

Then the action reported in A[2, 0], i.e. the numeric value corresponding to the action f_send_all, will be read. This means that recognition has occurred.

2) EXAMPLE OF RECOGNITION IN THE EVENT THE STREAM DIFFERS FROM THE RECORDS: 0x04 0x01

First read value is 04.

Being in an initial condition, it is used as an index of the matrix as well as of the vector.

The adopted Matrix/Vector pair is in the position 1 of the above reported list.

The row index of matrix A is determined by the element which has been read, i.e. Row A =04, i.e. the fourth row.

The column index of matrix A is determined by the value contained by vector B at the position corresponding to the element which is read, i.e. Column A=B[04]=X. Therefore the stream is not recognized.

3) EXAMPLE OF RECOGNITION IN THE EVENT THE STREAM DIFFERS FROM THE RECORDS: 0x01 0x05 0x03

The first read value is 01.

Being in an initial condition, it is used as an index of the matrix as well as of the vector.

The adopted pair Matrix/Vector is in the position 1 of the above reported list.

The row index of matrix A is determined by the element which has been read, i.e. Row A =04, i.e. the fourth row.

The column index of matrix A is determined by the value contained by vector B at the position corresponding to the element which is read, i.e. Column A =B[0x01]=0, i.e. the 0-th column.

Therefore, the value reported in A[1, 0], i.e. 0 will be read. Said value is the successive index of vector B.

- 39 -

Next, the action reported in A[1, 0] i.e. the numeric value corresponding to the action next(1) will be read.

Therefore, the position shall be shifted to the next value and the Matrix/Vector pair which is at position 2 in the above reported list will be used.

5 Read value is 05.

The row index of Matrix A is determined by the element which has been read, i.e. Row A = 05, i.e. the fifth row.

10 The column index of Matrix A is determined by the value contained in vector B at the position corresponding to the value reported in A[1, 0] obtained in the previous step. Column A = B[0] = 0.

Thus, the value reported in A[5, 0], i.e. X will have to be read. Therefore, the stream is not recognized.

15 Hence, using a direct access technique on matrices, easily operable in a microchip, the pattern recognizer is able to recognize the acceptability or the non acceptability of the input stream in a completely deterministic manner, in a number of accesses to matrices and vectors equaling the number of elements that are recognized in the same stream.

* * *

Herebelow, reference will be again made to figure 9.

20 Element 205:

It is the component for monitoring and acquisition of the communication frames. By means of this apparatus, an example of which has already been described in detail with reference to the preceding figures from 4 to 8B, the data acquisition also at an application level is made possible, i.e. the piece of information related to the layers 4-7 of the OSI standard. Such apparatus will be able to accept commands as CONNECT, SEND, RECEIVE and CLOSE in the event high layer application protocols have to be managed and coordinated.

Element 206 (Access control):

30 This element, starting from the recognition result operated by element 204, performs the forwarding action associated to such recognition, or the refusal action associated to the failed recognition.

In the event of acceptance the communication frame will be forwarded to the server of reference.

35 In the event of refusal, the communication frame will be returned to the sender, together with possible explanations of the refusal. In fact, by virtue of the

- 40 -

adopted <item>/<action> structure, it will be possible to associate actions, even complex ones as the construction of answer streams.

Element 207 (Access coordination):

5 This element, starting from the recognition result operated by element 204, performs the coordinating action associated to such recognition.

Such coordinating action relates to the individuation of the parameters to be forwarded to the server for the required coordination, individuation of the sender, formatting of the parameters to be forwarded, sending of parameters, acquisition of the answer from the server and forwarding of the obtained answer to
10 element 204 for a possible prosecution of the recognition.

This approach is made possible by means of the second introduced notation, as by virtue of this notation actions can be associated, even complex ones as the construction of streams to be forwarded to specific network accessible servers. The coordinating element proves useful when the apparatus is used to manage
15 communication among applications, therefore on high layer protocols (as those between client and server applications transferred on a TCP layer). In fact, in this event the apparatus, by virtue of the actions associated to input stream recognition, can operate changes in the stream for its re-forwarding to other application servers provided with different application protocols. A typical event occurs when the
20 mutual operativity and the application cooperation have to be managed in a heterogeneous context, and where different "application servers" or different broker devices need to coexist (here referring also to the various CORBA -Common Object Request Broker Architecture- implementations, always not fully compatible among them) in presence of client applications often designed to converse using old
25 application protocols.

The present invention has been described hereto with reference to one of its embodiments, given as non-limiting examples.

Furthermore, it is intended that there are other possible embodiments and kind of services falling within the protective scope of the present industrial
30 property right.

For instance, it might be provided that the access control device is implemented using a board installed on the processor where the "client" applications are operating in a context of the client-server type.

In this way, the fact that the access control device can be programmed by the
35 client computer administrator can be guaranteed, in order to activate the control/co-

- 41 -

ordination/documentation exclusively on the communications that are deemed "important" to control/co-ordinate/document.

As an example, the client administrator can decide:

5 - which communications, and therefore which application services are to be enabled in input to the client;

 - on which communications, and therefore on which application services, the documentation is to be enabled;

10 - on which communications, and therefore on which application services, specific functions such as authentication, electronic signature etc. are to be programmed;

15 In the event that there are service centres supplying application services, also provided with the access control device according to the present invention, the client administrator can decide whether to enable certification services of the application services carried out by the objective confirmation of the communication, given by the comparison of what was documented by the client and what was documented by service centre.

As an example, the client administrator can:

20 - decide to disable the access to certain WEB server, i.e. to certain WEB pages made available from a WEB server,

 - decide to enable the documentation of the commercial operations he carried out to certain WEB sites, and

 - set the application services for which it is necessary to authenticate the transaction by electronic signature.

APPENDIX A

1. II level language grammar

The language consists of: *types* for data representation; *operators* and *rules* for comprising expressions; *structures* for program flow control; *function commands* and *procedures*.

1.1. Data types

Types can be divided into three classes: representation of numbers, representation of strings and representation of sets.

Types for representation of numbers

Types for representation of numbers are the following:

WORD	LONG
WORD_HL	LONG_HL
WORD_LH	LONG_LH

The **WORD** type represents integers within the range $[2^{-15} - 2^{15}]$. The width of a **WORD** is of 2 bytes. Distinction between HL and LH indicates the position of the most representative byte, i.e. the first in HL and the second in LH.

The **LONG** type represents integers of a very high range $[2^{-31} - 2^{31}]$. The width of a **LONG** is of 4 bytes. Distinction between HL and LH indicates the position of the most representative byte i.e. the first in HL and the last in LH. All other bytes follow in the order of representation.

Specification HL/LH takes into account the various representation rules of the data on a frame by the various network protocols. The user, having these types, will not have to worry about operations related to the reading of the various formats.

Types for representation of strings

Types for representation of strings are the following:

BYTE	BYTE ()
STRING	

The first two types are byte-oriented, the last three are string-oriented.

BYTE indicates the single byte; when followed by a number within round brackets, indicates a numerically defined byte sequence.

STRING indicates a string of characters.

Types for representation of sets

Types for representation of sets are the following:

ENUM

The **ENUM** type represents the sets of elements of 5 types: **WORD**, **LONG**, **BYTE**, **BYTE_STREAM**, **STRING**. Syntax for its use is the following:

```
ENUM <name> <type>
name1, name2, . . . . . , nameN
END
```

For instance, a set of IP addresses can be represented as follows:

```

ENUM ip_address BYTE_STREAM
    {192,0,10,23},
    {192,0,11,24},
    {192,0,13,123},
    {192,0,1,23},
    {192,0,10,323},
    ...
    {192,0,15,23}

END

```

```

ENUM name_host STRING
    "CLIENT1","CLIENT2",....."CLIENTn"

END

```

1.2. Operators and expressions

Operators can be divided in three classes:

arithmetic:	+	-	*	/	=
bit by bit:		&			
on strings:	@	<<			

Operators + and - have the same priority, lower than that of * and /. All arithmetical operators are associative left to right, except for the allocation operator = that follows the opposite direction.

Operator & indicates the bit by bit AND; operator | indicates the bit by bit inclusive OR. In terms of priority, the former is on the same level of *, the latter on the same level of +.

Binary operator @ indicates concatenation between two variables, to be treated as two strings in binary representation. Binary operator << indicates allocation among strings. For instance,

```

BYTE(6) string1;
STRING string2;
WORD_HL num;
STRING string3;

```

Once values have been allocated to string1 , string3 and num, the following operation can be performed:

```

string3 << string1 @ string2 @ num ;

```

Notice the ; at the end of every command.

Priority and associability rules referring to each operator can be modified in a single expression using round brackets (apart from operators << and @ that do not allow brackets).

For a closer examination of the forming and the use of expressions deriving from the above-listed operators see examples herebelow.

1.3. Control Structures

In the II level language there is a single control structure having the following processing syntax:

- 44 -

```

TEST(<namevar>)
    IN <range> : control sequence
    IN <range> : control sequence
    .....
    .....
    DEFAULT : control or blank sequence ending with ;

END

```

The first argument <namevar> indicates the name of a previously declared variable, to which a value was given. On the basis of the latter the test will define whether it belongs to one of the **IN blocks** herebelow (in this case the block-associated control sequence shall be executed), or to the default block (in this case the control sequence associated to the default block shall be executed).

The argument <range> can be a variable of the **ENUM** type, or a string-type constant, or a number or a numeric range indicated in square brackets. In the two latter cases (number or numerical range) the number of bytes referring to the basic comparison is to be indicated in square brackets.

If the value of the <namevar> variable belongs to one of the specified <range> the sequence of commands associated thereto is executed. In turn, it has to be noted that a sequence of commands cannot include a test. Moreover, also the sequence of commands associated to the mandatory block of **DEFAULT**, a block that is executed even in case no one of the previously prompted **IN blocks** is executed, can be blank, meaning that a space and a final semicolon follow the double colon :. In this event no command will be executed.

An example of the use of the **TEST** structure is reported herebelow:

```

TEST(ip_source)
    IN ip_address: ;
    IN "\0d192\0d.0\0d2\0d32" : RETURN 0;
    IN 90-200 [4] :
        GET(0, eth_type);
        PRINT(eth_type);
    DEFAULT: RETURN -1;

END

```

The ip_source variable is of the **BYTE(4)** type and it is assumed to have been previously prompted and allocated. The ip_address variable is of the **ENUM** type; it has been already defined and allocated in the preceding example. The program idles if the ip_source value belongs to the ip_address set; it gives 0 if it is 192.0.2.32, written as string; executes two commands if it is within the range 90 – 200; in all the other events it gives –1.

1.4. Functions and commands

Second level language functions are of two types:

- functions of internal library analyseflow.lib;
- functions of an external dll linkable to the program.

Internal library functions are as follows:

- **MOVER**(mode, expression)

- 45 -

```

-      GET(mode, <namevar>)
-      PUT(mode, <namevar>)
-      PRINT(<namevar>)

```

Apart from **PRINT**, all functions adopt **mode** as parameter; it indicates an access channel to a reference data stream according to which the function specific action is to be executed. The channel can be a local one: e.g. **mode=1** identifies a local memory buffer; or remote: e.g.. **mode=1** identifies a TCP connection opened with a client, or a connection opened with a remote DBMS. Besides a predetermined set of access channels, the user can define specific TCP services. This operation is allowed by the command **#listen** followed by a number identifying a TCP service.

The **MOVER** function shifts the cursor associated to the data stream selected with **mode**, for a number of bytes that equals the one which is the result of the expression of the second parameter. The function defines the current position of each cursor according to which a function defines the current position of each cursor, according to which the other functions will operate.

The **GET** function gives a value to the variable indicated with the **<namevar>** parameter taking it from the stream indicated with the **mode** parameter, in the current position of the cursor associated to the stream itself.

The **PUT** function gives a value to the variable indicated with the **<namevar>** parameter, data stream indicated with **mode** parameter, in the current position of the cursor associated to the stream itself.

The **PRINT** function prints to video the value of the **<namevar>** variable previously defined and initialized.

The program further allows functions from an external dll. These functions are inserted in a preset buffer and have predetermined names (**u_f_1**, **u_f_2**, etc.). The dll has to be constructed so as to let this operation occur correctly. In particular:

- it has to be constructed as a succession of functions, each having a serial number which is same of a host function of the preset buffer;
- it has to be constructed in Visual C++ language;
- each function forming it has to have the following structure:

```
int namefunct(int numparameters, char **parvett, long *dim_vett)
```

The first parameter is an integer, indicating the number of effective parameters required by the function to carry out the operations that are up to it; the second parameter is a pointer to an array of character pointers; the dimension of the array is numparameters; each pointed buffer is a parameter. Finally, the third parameter is a pointer to an array of long integers. Each element of the array indicates the dimension of the string representing the corresponding parameter.

The **#DEFINE** command allows to rename these functions with names that can be used inside the program.

1.5. Procedures

The II level language enables to define procedures according to the following syntax:

```
START <nameproc>
```

```
    Set of commands forming the procedure.
```

```
END
```

A procedure can be recalled by another with the **<nameproc>** command. I.e., a procedure defines a homonymous command provided for the purpose. E.g.:

- 46 -

```

TEST(ip_source)
    IN ip_address: proc1();
    DEFAULT: RETURN -1;

END

```

In the example proc1() indicates the recalling of procedure proc1 defined in the program. For further explanation see herebelow the subparagraph procedure on the program structure and the final example.

1.6. The program structure

The program structure in the second level language, as it can be seen in the example herebelow, is the following:

```

DEFINE BLOCK
LISTEN BLOCK
ENUM TYPES DECLARATION BLOCK
START MAIN PROCEDURE
DECLARATION OF VARIABLES
COMMAND SEQUENCE
END MAIN PROCEDURE
SUBPROCEDURES BLOCK

```

or, more unequivocally:

```

#define my_funct0 u_f_0
#define my_funct0 u_f_1
.....
#define my_funct0 u_f_n

#listen tcp_serv1
#listen tcp_serv2
#listen tcp_serv3

enum <name1> type
name11,name12,....,name1n
end
.....
enum <name1> type
name11,name12,....,name1n
end

START main
    DECLARATION OF VARIABLES
    PROGRAM COMMANDS
END

START proc1
    PROCEDURE COMMANDS
END
.....
START procn
    PROCEDURE COMMANDS
END

```

1.7. The run-time performance of the language

A program in that language is a straight-line program where all the instructions look the same time at execution level. In particular the **test** instruction took a constant time a execution level, independently, from the number of **IN** clauses and from the type and dimension of **IN** clauses (string, enum,...).

- 47 -

CLAIMS

1. A network access control device through deterministic recognition of application frames satisfying a set of predetermined rules comprising:

5 - means (205) for monitoring and interpretation of the application frames to recognize;

 - means (201) for storing predetermined rules;

 - means (202) for compiling the predetermined rules in a direct access data structure;

10 - means (203) for storing said direct access data structure; and

 - means (204) for comparing the application frames to be recognized with said direct access data structure,

 wherein the recognition is able to be performed on any frame component and the direct access data structure allows an access time substantially independent from
15 the number of rules.

2. The access control device according to claim 1, characterized in that said compiling means (202) of the predetermined rules comprise:

20 - conversion means, for converting the predetermined rules in a set of basic sequences of numerical identifiers; and

 - compression means, for compressing the set of sequences thus obtained in a direct access data structure.

3. The access control device according to claim 1 or 2, characterized in that it
25 further comprises forwarding means, for forwarding the application frame when recognized and return-to-sender means, for returning of the application frame when not recognized.

4. The access control device according to claim 3, characterized in that said
30 return-to-sender means, for returning the application frames when not recognized, return information related to the reason of the failed forwarding.

5. The access control device according to any of the preceding claims, characterized in that the predetermined rules are stored as pairs of <object>/<action>
35 fields.

- 48 -

6. The access control device according to claim 5, characterized in that the predetermined rules are stored as pairs of <data type>/<data value> fields.

5 7. The access control device according to claim 5 or 6, characterized in that the predetermined rules include one or more joker values.

8. The network access monitoring device according to claim 5, characterized in that the field <action> refers to the minimal set of commands

- **Push**

10

<value>

<variable>

<reading position>

<value at the reading position>

- **Pop**

15

<variable>

<reading position>

<at the reading position>

- **And**

- **Mul**

20

- **Add**

- **Equal**

- **Next**

- **F_send_all**

- **F_dynamic.**

25

9. The access control device according to claims 2 and 5, characterized in that the direct access data structure is represented through a matricial structure comprising object fields and action fields.

30

10. The access control device according to any of the preceding claims, characterized in that the means (205) for monitoring and interpretation of the application frames comprise:

35

a) a data packets monitoring device (9) at a layer corresponding to the OSI layer 2, said data packets comprising control frames and information frames, wherein the control and information frames contain a header portion and a body portion, said

- 49 -

header portion allowing the distinction between an information frame and a control frame;

b) a control unit (15) receiving as an input the data coming from the monitoring device (9) and comprising means for the discrimination of the control frames from the information frames;

c) a dating unit (16) connected to the control unit (15) and associating a monitoring time to the control frames and to the information frames;

d) a discriminated data storing unit (17), storing the control and the information frames and the monitoring time thereof, bidirectionally connected to the control unit (15);

e) a predetermined data storing unit (18), bidirectionally connected to the control unit (15), said predetermined data representing possible interpretations of the information frames contained in the discriminated data storing unit (17);

f) means for comparing, by the control unit (15), said predetermined data stored in the storing unit (18) with the data contained in the body portion of the information frames stored in the discriminated data storing unit (17), thus reconstructing the information frames according to their specific application syntax;

g) means for ordering, according to the time and kind of communication, the information frames reconstructed according to their specific application syntax, thus reconstructing application sequences occurred between a determined source processor and a determined destination processor; and

h) means for ordering said information frames ordered according to the time and kind of communication also according to a logical criterion, thus reconstructing the logical path of said application sequences occurred between a determined source processor and a determined destination processor.

11. The access control device according to claim 10, characterized in that said means for ordering said information frames according to a logical criterion comprise means for reciprocally comparing the body portion of the information frames.

12. The access control device according to claim 10, characterized in that said means for ordering said information frames according to a logical criterion comprise means for comparing each sequence of body portions of the information frames with a set of predetermined sequences, said predetermined sequences representing possible interpretations of the information frames sequences contained in the

- 50 -

discriminated data storing unit (17), said predetermined sequences being contained in said predetermined data storing unit (18).

- 5 13. The access control device according to any of the preceding claims, characterized in that it is implemented using a board installed on the processor on which the client applications operate.




FIG 1




FIG 2

- 3/12 -




FIG.3

- 4/12 -




FIG 4

- 5/12 -




FIG 5




FIG 6

- 7/12 -




FIG 7




FIG 8A




FIG 8B




FIG. 9

- 10/12 -




FIG.10A

	0	1	2	3	4
A	×		×		
B	×		×		
C		×			×
D			×		
E			×		

FIG. 10B




FIG.11

- 12/12 -

0	1	2	3	4	5	6	7	8	9	0A	0B	0C
1: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (0A,400F) (84,4010) (93,4011) (A0,4012) (01,4013) (00,8002) (50,8003)												
2: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (0A,400F) (84,4010) (93,4011) (A0,4012) (02,4013) (00,8002) (19,8003)												
3: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (0A,400F) (84,4010) (93,4011) (A0,4012) (02,4013) (00,8002) (89,8003)												
4: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (0A,400F) (84,4010) (93,4011) (A0,4012) (02,4013) (00,8002) (8A,8003)												
5: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (0A,400F) (84,4010) (93,4011) (A0,4012) (02,4013) (00,8002) (8B,8003)												
6: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (01,4013) (00,8002) (14,8003)												
7: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (01,4013) (00,8002) (15,8003)												
8: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (01,4013) (00,8002) (17,8003)												
9: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (02,4013) (00,8002) (19,8003)												
0A: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (02,4013) (00,8002) (50,8003)												
0B: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (03,4013) (00,8002) (50,8003)												
0C: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (03,4013) (00,8002) (A1,8003)												
0D: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (03,4013) (00,8002) (A2,8003)												
0E: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (03,4013) (08,8002) (01,8003)												
0F: (08,000C) (00,000D) (06,4009) (84,400C) (93,400D) (C8,400E) (14,400F) (84,4010) (93,4011) (A0,4012) (03,4013) (00,8002) (17,8003)												
10: (08,000C) (06,000D)												
11: (08,000C) (00,000D) (01,4009)												

FIG.12

INTERNATIONAL SEARCH REPORT

International Application No
PCT/IT 99/00262

A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 H04L29/06 H04L12/26

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
IPC 7 H04L

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	US 5 793 954 A (BAKER PETER D ET AL) 11 August 1998 (1998-08-11) column 2, line 36 -column 3, line 43 column 4, line 1-42 column 5, line 56 -column 6, line 40 column 9, line 13 -column 10, line 27 ---	1-13
A	PRUFER R J: "NETWORK ADVISOR PROTOCOL ANALYSIS: DECODES" HEWLETT-PACKARD JOURNAL,US,HEWLETT-PACKARD CO. PALO ALTO, vol. 43, no. 5, page 34-40 XP000349772 page 37, left-hand column, line 1 -page 38, right-hand column, line 16 --- -/--	1-13

☒ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search

21 January 2000

Date of mailing of the international search report

31/01/2000

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax: (+31-70) 340-3016

Authorized officer

Lázaro López, M.L.

INTERNATIONAL SEARCH REPORT

Inter nal Application No

PCT/IT 99/00262

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	<p>SUNIL BHAT: "THE NETWORK ADVISOR ANALYSIS AND REAL-TIME ENVIRONMENT" HEWLETT-PACKARD JOURNAL, US, HEWLETT-PACKARD CO. PALO ALTO, vol. 43, no. 5, page 29-33 XP000349771 page 29, right-hand column, line 34 -page 30, right-hand column, line 14 page 31, left-hand column, line 40 -right-hand column, line 38 ---</p>	1-13
A	<p>EP 0 595 509 A (LANNET DATA COMMUNICATIONS LTD) 4 May 1994 (1994-05-04) column 2, line 48 -column 3, line 40 column 5, line 1-19 -----</p>	1-13

INTERNATIONAL SEARCH REPORT

information on patent family members

International Application No

PCT/IT 99/00262

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
US 5793954 A	11-08-1998	AU 1355097 A EP 0868799 A US 6000041 A WO 9723076 A US 5781729 A	14-07-1997 07-10-1998 07-12-1999 26-06-1997 14-07-1998
EP 0595509 A	04-05-1994	IL 103467 A US 5489896 A	31-03-1996 06-02-1996